

Proposal:240244
J/P Num:33536(04)
Counties:GRADY

Let Date:October 17, 2024
Proj. Num:STP-226C(127)CI

Call Order:410

Description:BRIDGE AND APPROACHES

COUNTY ROAD (EW-142): OVER TRIBUTARY TO LITTLE WASHITA RIVER,
1.5 MILES WEST OF THE SH-19 JUNCTION NEAR EAST NINNEKAH.
PROJECT LENGTH = 0.075 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001 ROADWAY			
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	2,454.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	587.000	CY
0040 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050 221(E)2600	TEMPORARY SILT DIKE	294.000	LF
0060 221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	68.000	CY
0070 230(A)7200	SOLID SLAB SODDING	5,484.000	SY
0080 233(A)0200	VEGETATIVE MULCHING	1.580	AC
0090 303(A)1200	AGGREGATE BASE TYPE A	207.000	CY
0100 307(K)4200	STABILIZED SUBGRADE	1,393.000	SY
0110 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	382.000	TON
0120 408 8100	PRIME COAT	817.000	GAL
0130 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	242.000	TON
0140 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	117.000	TON
0150 509(D)0500	CLASS C CONCRETE	10.000	CY
0160 602(B)2310	REVTMENT MATTRESSES	633.000	SY
0170 613(B)5552	72" CORR. GALV. STEEL PIPE	86.000	LF
0180 613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	32.000	LF
0190 613(P)7450	21" X 15" GALV. STEEL CULV. END SEC.ARCH	2.000	EA
0200 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0210 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	694.000	SY
0220 624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	539.000	LF
0002 BRIDGE			
0230 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	1,600.000	CY
0240 501(D)1500	UNCLASSIFIED BACKFILL	780.000	CY
0250 508 9140	PREFABRICATED METAL ARCH CULVERT	55.000	LF
0260 509(B)0320	CLASS A CONCRETE	121.400	CY
0270 511(A)2210	REINFORCING STEEL	12,160.000	LB
0280 514(A)5220	PILES, FURNISHED (HP 12X53)	2,114.000	LF
0290 514(B)5320	PILES, DRIVEN (HP 12X53)	2,114.000	LF
0300 514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0310 602(B)2320	REVTMENT MATTRESS	1,205.000	SY
0320 613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	164.000	LF
0330 613(I)6310	6" NON-PERF.PIPES UNDERDRAIN RND.	60.000	LF
0340 619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003 TRAFFIC			
0350 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	207.000	SD
0360 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,863.000	SD
0370 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	414.000	SD
0380 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	828.000	SD
0390 880(E)6600	WARNING LIGHTS(TYPE A)	2,070.000	SD
0400 882(A)8200	PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EA

Proposal:240244
J/P Num:33536(04)
Counties:GRADY

Let Date:October 17, 2024
Proj. Num:STP-226C(127)CI

Call Order:410

Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW-142): OVER TRIBUTARY TO LITTLE WASHITA RIVER,
1.5 MILES WEST OF THE SH-19 JUNCTION NEAR EAST NINNEKAH.
PROJECT LENGTH = 0.075 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0004 STAKING			
0410 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005 CONSTRUCTION			
0420 641 2110	MOBILIZATION	1.000	LSUM