Proposal:240256 **Let Date:**November 14, 2024 **Call Order:**550
J/P Num:36360(04) **Proj. Num:**SBR-244C(112)SB
Counties:MCCLAIN
Description:BRIDGE REHABILITATION
SH-24: OVER FINN CREEK, 1.0 MILE WEST OF
THE SH-74 JUNCTION NEAR MAYSVILLE.
PROJECT LENGTH = 0.178 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	150.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	200.000	CY
0030	205(A)6210	TYPE A-SALVAGED TOPSOIL	130.000	CY
0040	221(B)2300	TEMPORARY SILT FENCE	1,486.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	500.000	LF
0060	230(A)7200	SOLID SLAB SODDING	1,166.000	SY
0070	310(B)5300	SUBGRADE, METHOD B	3,225.000	SY
0080	407(B)7300	TACK COAT	192.000	GAL
0090	408 8100	PRIME COAT	457.000	GAL
0100	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	222.000	TON
0110	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	365.000	TON
0120	412 3100	COLD MILLING PAVEMENT	1,920.000	SY
0140	619(B)6396	REMOVAL OF GUARDRAIL	400.000	LF
0150	619(C)6600	SAWING PAVEMENT	1,440.000	LF
0160	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	700.000	LF
0170	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0180	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0190	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	14.000	EA
0002	BRIDGE 'A'			
0200	501(G)1800	CLSM BACKFILL	74.400	CY
0210	502(B)3320	(PL)FALSEWORK JACKING	1.000	LSUM
0220	504(A)5200	APPROACH SLAB	227.800	SY
0230	504(B)5300	SAW-CUT GROOVING	801.000	SY
0240	504(D)5420	CONCRETE RAIL (TR4)	450.500	LF
0250	506(A)7200	STRUCTURAL STEEL	790.000	LB
0260	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	8.000	EA
0270	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	8.000	EA
0280	509(A)0210	CLASS AA CONCRETE	141.000	CY
0290	509(D)0510	CLASS C CONCRETE	20.000	CY
0300	511(B)2310	EPOXY COATED REINFORCING STEEL	55,850.000	LB
0310	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0320	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0330	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	513.000	SY
0340	517 9110	ELASTOMERIC COATING	814.000	SF
0350	518(B)0300	SEALED EXPANSION JOINTS	70.340	LF
0360	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	30.000	LF
0370	520(C)1400	EPOXY RESIN, ABOVE WATER	2.400	GAL
0380	523(A)3200	SEALER CRACK PREPARATION	137.000	LF
0390	523(B)3300	SEALER RESIN	1.600	GAL
0400	540 8112	(PL)REPAIR BRIDGE ITEMS	18.000	SY
0410	540 8120	(PL)REPAIR BRIDGE ITEM (TYPE A)	30.000	EA
0420	540 8144	(PL)REPAIR BRIDGE ITEM (TYPE B)	14.000	SY
0430	601(B)1230	TYPE I-A PLAIN RIPRAP	630.000	TON
0440	601(C)1310	TYPE I-A FILTER BLANKET	100.000	TON
0450	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:240256 **Let Date:**November 14, 2024 **Call Order:**550
J/P Num:36360(04) **Proj. Num:**SBR-244C(112)SB
Counties:MCCLAIN
Description:BRIDGE REHABILITATION
SH-24: OVER FINN CREEK, 1.0 MILE WEST OF
THE SH-74 JUNCTION NEAR MAYSVILLE.
PROJECT LENGTH = 0.178 MILES

Line #		Item Description	Quantity	Unit
0003	SIGNING AND STRIPING			
0460	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	6.000	EA
0470	850(A)1200	SHEET ALUMINUM SIGNS	22.000	SF
0480	851(C)2420	2 1/4" SQUARE TUBE POST	56.000	LF
0490	856(A)8204	TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	3,250.000	LF
0004	TRAFFIC CONTROL			
0500	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	17,520.000	SD
0510	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,200.000	SD
0520	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	240.000	SD
0530	880(B)6330	CONSTRUCTION SIGNS 33.0 SF & OVER	600.000	SD
0540	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0550	880(E)6600	WARNING LIGHTS(TYPE A)	1,440.000	SD
0560	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	388.000	SD
0005	STAKING			
0570	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0580	641 2100	MOBILIZATION	1.000	LSUM