Proposal:240260 **Let Date:**April 17, 2025 **Call Order:**871
J/P Num:23107(07) **Proj. Num:**NHPP-168N(179)FP
Counties:SEQUOYAH
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
US-59: OVER HOG CREEK, FROM THE INTERSECTION OF US-64,
EXTEND NORTH IN SALLISAW.
PROJECT LENGTH = 3.399 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	56,312.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	31,729.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	11,020.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	4.000	EA
0070	221(E)2600	TEMPORARY SILT DIKE	840.000	LF
0080	221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	107.000	CY
0090	229 6100	DITCH LINER PROTECTION	1,978.000	LF
0100	230(A)7200	SOLID SLAB SODDING	131,802.000	SY
0110	232(B)9300	SEEDING METHOD B	27.210	AC
0120	233(A)0200	VEGETATIVE MULCHING	27.210	AC
0130	241 3100	MOWING	54.420	AC
0140	303(A)1200	AGGREGATE BASE TYPE A	12,622.000	CY
0150	307(A)3200	FLY ASH	2,030.000	TON
0160	307(D)3500	LIME	153.000	TON
0170	307(E)3600	CEMENTITIOUS STABILIZED SUBGRADE	78,292.000	SY
0180	307(G)3800	LIME PRETREATMENT	15,659.000	SY
0190	325 0100	SEPARATOR FABRIC	66,685.000	SY
0200	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	12,332.000	TON
0210	407(A)7200	FOG SEAL	4,125.000	GAL
0220	407(B)7300	TACK COAT	21,321.000	GAL
0230	408 8100	PRIME COAT	46,877.000	GAL
0240	409(A)9200	FABRIC REINFORCEMENT	13,399.000	SY
0250	409(B)9300	BITUMINOUS BINDER	4,174.000	GAL
0260	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	8,255.000	TON
0270	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	31,554.000	TON
0280	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	5,410.000	TON
0290	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	5,748.000	TON
0300	412 3100	COLD MILLING PAVEMENT	41,586.000	SY
0310	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	4,596.000	LF
0320	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	4,596.000	SY
0330	414(G)5800	P.C. CONCRETE FOR PAVEMENT	605.000	CY
0340	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	80.000	CY
0350	509(B)0300	CLASS A CONCRETE	216.000	CY
0360	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	3.000	CY
0370	509(D)0500	CLASS C CONCRETE	214.000	CY
0380	511(A)2200	REINFORCING STEEL	19,906.000	LB
0390	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	1,796.000	LF
0400	609(B)4360	2'-8" COMB.CRB.& GUT.(6" BARRIER)	5,448.000	LF
0410	609(B)4370	2'-8" COMB.CRB.& GUT.(6" MNTBLE)	2,100.000	LF
0420	610(A)5200	4" CONCRETE SIDEWALK	3,305.000	SY
0430	610(B)5310	6" CONCRETE DRIVEWAY	1,298.000	SY
0440	610(C)5400	4" CONCRETE DIVIDING STRIP	649.000	SY
0450	610(C)5410	6" CONCRETE DIVIDING STRIP	467.000	SY
0460	610(I)6000	TACTILE WARNING DEVICE-NEW	300.000	SF

Proposal:240260 **Let Date:**April 17, 2025 **Call Order:**871
J/P Num:23107(07) **Proj. Num:**NHPP-168N(179)FP
Counties:SEQUOYAH
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
US-59: OVER HOG CREEK, FROM THE INTERSECTION OF US-64,
EXTEND NORTH IN SALLISAW.
PROJECT LENGTH = 3.399 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	610(J)6100	(PL) STAMPED CONCRETE FINISH	223.000	SY
0480	611(A)7210	MANHOLE (4' DIA.)	2.000	EA
0490	611(A)7220	MANHOLE (6' DIA.)	1.000	EA
0500	611(B)7300	ADD'L.DEPTH IN MANHOLE (4' DIA.)	1.000	VF
0510	611(G)0264	INLET W/SMALL JCT. BOX, CI, DES.2	2.000	EA
0520	611(G)0304	INLET W/SMALL JCT. BOX, CI, DES.3	7.000	EA
0530	611(G)0308	INLET W/SMALL JCT. BOX, CI, DES.3(B)	2.000	EA
0540	611(G)0354	INLET (SMD-TYPE 2)	4.000	EA
0550	611(G)7710	INLET CI DES. 1 (STD)	2.000	EA
0560	611(G)7754	INLET CI DES. 2 (STD)	7.000	EA
0570	611(G)7786	INLET CI DES. 3 (STD)	4.000	EA
0580	611(G)7790	INLET CI DES. 3 (B)	1.000	EA
0590	611(G)8070	INLET CDI 30SK RCB DES. 1	1.000	EA
0600	611(H)0410	ADD'L DEPTH IN INLET CI DES. 1	3.000	VF
0610	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	9.000	VF
0620	611(H)0422	ADD'L DEPTH IN INLET CI DES. 3	7.000	VF
0630	611(H)0580	ADD'L DEPTH IN INLET CDI RCB 30SK DES. 1	3.000	VF
0640	611(H)0944	ADD'L DEPTH IN INLET W/SJB, CI, DES. 3	3.000	VF
0650	611(H)0948	ADD'L DEPTH IN INLET W/SJB, CI, DES. 3(B)	2.000	VF
0660	611(L)1600	JUNCTION BOXES	30.000	CF
0670	613(A)5208	18" R.C.PIPE CLASS III	2,802.000	LF
0680	613(A)5216	24" R.C.PIPE CLASS III	166.000	LF
0690	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	20.000	LF
0700	613(B)5508	18" CORR. GALV. STEEL PIPE	1,420.000	LF
0710	613(B)5516	24" CORR. GALV. STEEL PIPE	628.000	LF
0720	613(B)5524	30" CORR. GALV. STEEL PIPE	70.000	LF
0730	613(B)5528	36" CORR. GALV. STEEL PIPE	98.000	LF
0740	613(B)5552	72" CORR. GALV. STEEL PIPE	480.000	LF
0750	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	1,488.000	LF
0760	613(B)5608	24" X 18" CORR. GALV. STEEL PIPE ARCH	124.000	LF
0770	613(B)5612	28" X 20" CORR. GALV. STEEL PIPE ARCH	510.000	LF
0780	613(B)5620	42" X 29" CORR. GALV. STEEL PIPE ARCH	502.000	LF
0790	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	7,663.000	LF
0800	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	570.000	LF
0810	613(M)6960	TYPE A4 CULVERT END TREATMENT	104.000	EA
0820	613(M)6964	TYPE B4 CULVERT END TREATMENT	26.000	EA
0830	613(M)6968	TYPE C4 CULVERT END TREATMENT	12.000	EA
0840	613(M)6972	TYPE D4 CULVERT END TREATMENT	2.000	EA
0850	613(M)6980	TYPE AA4 CULVERT END TREATMENT	4.000	EA
0860	613(M)6984	TYPE BB4 CULVERT END TREATMENT	4.000	EA
0870	613(M)7008	TYPE B6 CULVERT END TREATMENT	1.000	EA
0880	613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	2,540.000	CY
0890	613(V)8000	TRENCH EXCAVATION	4,010.000	CY
0900	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0910	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	2,902.530	SY
0920	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	39,478.000	SY

Proposal:240260 **Let Date:**April 17, 2025 **Call Order:**871
J/P Num:23107(07) **Proj. Num:**NHPP-168N(179)FP
Counties:SEQUOYAH
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
US-59: OVER HOG CREEK, FROM THE INTERSECTION OF US-64,
EXTEND NORTH IN SALLISAW.
PROJECT LENGTH = 3.399 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0930	619(B)6396	REMOVAL OF GUARDRAIL	452.000	LF
0940	619(B)6464	REMOVAL OF 6" CONCRETE DIVIDING STRIP	129.000	SY
0950	619(C)6600	SAWING PAVEMENT	46,280.000	LF
0960	622(A)0220	2" PIPE RAILING	20.000	LF
0970	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	263.000	LF
0980	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0990	623(I)2000	GUARDRAIL BRIDGE CONNECTION-TYPE A	4.000	EA
1000	624(A)3200	FENCE-STYLE WWF	1,131.000	LF
1010	624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	76.000	LF
1020	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	2,504.000	LF
1030	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	457.000	LF
1040	624(C)3415	FENCE-STYLE SWF (4 SMOOTH WIRE)	438.000	LF
1050	624(E)3600	FENCE-STYLE CLF (4'HIGH, CLASS A)	628.000	LF
1060	624(E)3610	FENCE-STYLE CLF (5'HIGH, CLASS A)	119.000	LF
1070	624(E)3620	FENCE-STYLE CLF (6'HIGH, CLASS A)	65.000	LF
1080	629(A)7200	MAILBOX INSTALLATION-SINGLE	18.000	EA
1090	629(B)7300	MAILBOX INSTALLATION-MULTIPLE	10.000	EA
1100	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	42.000	EA
1110	629(E)7600	MAILBOX	46.000	EA

Proposal:240260 **Let Date:**April 17, 2025 **Call Order:**871
J/P Num:23107(07) **Proj. Num:**NHPP-168N(179)FP
Counties:SEQUOYAH
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
US-59: OVER HOG CREEK, FROM THE INTERSECTION OF US-64,
EXTEND NORTH IN SALLISAW.
PROJECT LENGTH = 3.399 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A' - NBI NO. 32300			
1120	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	80.000	CY
1130	501(G)1800	CLSM BACKFILL	122.000	CY
1140	503(A)4220	PRESTRESSED CONCRETE BEAMS (TYPE II)	537.000	LF
1150	504(A)5200	APPROACH SLAB	187.400	SY
1160	504(B)5300	SAW-CUT GROOVING	788.800	SY
1170	504(D)5420	CONCRETE RAIL (TR4)	351.000	LF
1180	506(A)7200	STRUCTURAL STEEL	1,050.000	LB
1190	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	8.000	EA
1200	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	16.000	EA
1210	507(C)8400	ELASTOMERIC BEARING PADS	16.000	EA
1220	509(A)0210	CLASS AA CONCRETE	183.000	CY
1230	509(B)0320	CLASS A CONCRETE	109.000	CY
1240	511(B)2310	EPOXY COATED REINFORCING STEEL	55,370.000	LB
1250	514(A)5210	PILES, FURNISHED (HP 10X42)	228.000	LF
1260	514(B)5310	PILES, DRIVEN (HP 10X42)	228.000	LF
1270	514(K)6200	(PL)PILOT HOLES	192.000	LF
1280	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
1290	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	625.000	SY
1300	516(A)8230	DRILLED SHAFTS 48" DIAMETER	106.000	LF
1310	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
1320	523(A)3200	SEALER CRACK PREPARATION	163.000	LF
1330	523(B)3300	SEALER RESIN	1.800	GAL
1340	601(B)1230	TYPE I-A PLAIN RIPRAP	1,490.000	TON
1350	601(C)1310	TYPE I-A FILTER BLANKET	190.000	TON
1360	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	84.000	LF
1370	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	18.000	LF
1380	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:240260 **Let Date:**April 17, 2025 **Call Order:**871
J/P Num:23107(07) **Proj. Num:**NHPP-168N(179)FP
Counties:SEQUOYAH
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
US-59: OVER HOG CREEK, FROM THE INTERSECTION OF US-64,
EXTEND NORTH IN SALLISAW.
PROJECT LENGTH = 3.399 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC			
1390	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	155.000	LF
1400	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	355.000	LF
1410	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	90.000	LF
1420	803(A)1210	PULL BOX(SIZE I)	3.000	EA
1430	803(A)1220	PULL BOX(SIZE II)	1.000	EA
1440	804(A)2200	STRUCTURAL CONCRETE	12.850	CY
1450	804(B)2300	REINFORCING STEEL	1,824.400	LB
1460	805(A)3208	REMOVAL OF PULL BOX	3.000	EA
1470	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
1480	806(A)4264	32'MH POLE,55'TS & 10'LMA(G.STL.)	1.000	EA
1490	806(A)4320	POLE & 35' TS MST.ARM(G.STL.)	1.000	EA
1500	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	3.000	EA
1510	809(A)7200	ROADWAY LUMINAIRE	1.000	EA
1520	810(A)8200	SERVICE POLE	1.000	EA
1530	811 9120	1/C NO.6 ELECT.COND.	200.000	LF
1540	811 9130	1/C NO.10 ELECT.COND.	1,715.000	LF
1550	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
1560	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
1570	830 2100	PEDESTRIAN PUSH BUTTON	4.000	EA
1580	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	4.000	EA
1590	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
1600	831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	2.000	EA
1610	833 5100	BACKPLATE	10.000	EA
1620	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,435.000	LF
1630	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	690.000	LF
1640	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	25.000	LF
1650	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	58.000	SF

Proposal:240260 **Let Date:**April 17, 2025 **Call Order:**871
J/P Num:23107(07) **Proj. Num:**NHPP-168N(179)FP
Counties:SEQUOYAH
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
US-59: OVER HOG CREEK, FROM THE INTERSECTION OF US-64,
EXTEND NORTH IN SALLISAW.
PROJECT LENGTH = 3.399 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC OPERATIONS			
1660	104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	60.000	DAY
1670	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	71,223.000	LF
1680	857(B)9300	CONSTRUCTION TRAFFIC STR.(PAINT)(ARROWS)	3.000	EA
1690	857(B)9320	CONSTRUCTION TRAFFIC STR.(PAINT)(SYMBOL)	4.000	EA
1700	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	200,127.000	LF
1710	857(C)9420	REMOVABLE PAVEMENT MARKING TAPE(ARROWS)	13.000	EA
1720	857(C)9440	REMOVABLE PAVEMENT MARKING TAPE(SYMBOLS)	1.000	EA
1730	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	500.000	EA
1740	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	27,822.000	LF
1750	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	3.000	EA
1760	857(F)9720	PAVEMENT MARKING REMOVAL(WORDS)	1.000	EA
1770	857(F)9730	PAVEMENT MARKING REMOVAL(SYMBOLS)	1.000	EA
1780	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	120.000	SD
1790	880(A)6220	ARROW DISPLAY(TYPE C)	365.000	SD
1800	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	11,315.000	SD
1810	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	6,935.000	SD
1820	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	16,060.000	SD
1830	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	15,695.000	SD
1840	880(C)6420	WING BARRICADES	2,920.000	SD
1850	880(D)6500	VERTICAL PANELS	18,250.000	SD
1860	880(E)6600	WARNING LIGHTS(TYPE A)	36,500.000	SD
1870	880(F)6700	DRUMS	36,500.000	SD
1880	880(G)6800	TUBE CHANNELIZERS	2,000.000	SD
1890	880(I)7000	FLAGGER	730.000	SD
1900	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	730.000	SD
0005	TRAFFIC SIGNING AND STRIPING			
1910	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	106.000	EA
1920	850(A)1200	SHEET ALUMINUM SIGNS	71.000	SF
1930	851(C)2415	2" SQUARE TUBE POST	135.000	LF
1940	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	14.000	EA
1950	856(A)8201	(SP) TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	69,434.000	LF
1960	856(A)8210	(SP) TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE)	1,253.000	LF
1970	856(A)8214	(SP) TRAFFIC STRIPE(MULTI-POLY)(12" WIDE)	967.000	LF
1980	856(A)8218	(SP) TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	583.000	LF
1990	856(B)8306	(SP) TRAFFIC STRIPE(MULTI-POLY.)(ARROWS)	48.000	EA
2000	856(B)8310	(SP) TRAFFIC STRIPE(MULTI-POLY.)(SYMBOLS)	8.000	EA
0006	STAKING			
2010	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION			
2020	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
2030	641 2110	MOBILIZATION	1.000	LSUM