Proposal: 240261 **Let Date:** November 21, 2024 **Call Order:** 585
J/P Num: 31895(04) **Proj. Num:** STP-269B(090)PM
Counties: STEPHENS
Description: BRIDGE AND APPROACHES
SH-53: OVER WALKER CREEK,
7.1 MILES WEST OF THE SH-53/ US-81
INTERSECTION NEAR CORUM.
PROJECT LENGTH = 0.407 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	8,465.960	CY
0030	202(B)2300	MUCK EXCAVATION	1,000.000	CY
0040	202(D)2500	UNCLASSIFIED BORROW	33,323.480	CY
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	221(B)2300	TEMPORARY SILT FENCE	1,865.000	LF
0070	221(E)2600	TEMPORARY SILT DIKE	276.000	LF
0080	221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	17.000	CY
0090	221(G)2800	TEMPORARY FIBER LOG	2,000.000	LF
0100	229 6100	DITCH LINER PROTECTION	1,960.320	LF
0110	230(A)7200	SOLID SLAB SODDING	27,052.490	SY
0120	233(A)0200	VEGETATIVE MULCHING	5.590	AC
0130	303(A)1210	AGGREGATE BASE TYPE A, PLANT MIXED	2,236.320	CY
0140	307(K)4200	STABILIZED SUBGRADE	18,956.760	SY
0150	325 0100	SEPARATOR FABRIC	9,913.790	SY
0160	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	510.690	TON
0170	407(B)7300	TACK COAT	1,990.290	GAL
0180	408 8100	PRIME COAT	9,113.310	GAL
0190	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	4,489.780	TON
0200	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,933.610	TON
0210	412 3100	COLD MILLING PAVEMENT	1,777.670	SY
0220	509(A)0200	CLASS AA CONCRETE	136.020	CY
0230	509(D)0500	CLASS C CONCRETE	254.870	CY
0240	511(A)2200	REINFORCING STEEL	14,430.500	LB
0250	514(H)5900	SHEET PILING, FURNISHED	128.000	SY
0260	514(I)6000	SHEET PILING, DRIVEN	128.000	SY
0270	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	188.000	TON
0280	613(B)5508	18" CORR. GALV. STEEL PIPE	96.000	LF
0290	613(B)5516	24" CORR. GALV. STEEL PIPE	162.000	LF
0300	613(B)5540	54" CORR. GALV. STEEL PIPE	140.000	LF
0310	613(B)5552	72" CORR. GALV. STEEL PIPE	198.000	LF
0320	613(H)6200	6" PERFORATED PIPE UNDERDRAIN ROUND	500.000	LF
0330	613(I)6305	6" NON-PERF.PIPE UNDERDRAIN RND.	100.000	LF
0340	613(M)6960	TYPE A4 CULVERT END TREATMENT	4.000	EA
0350	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0360	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	13,709.410	SY
0370	619(B)6396	REMOVAL OF GUARDRAIL	553.000	LF
0380	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	780.000	LF
0390	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0400	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0410	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	1,344.000	LF
0420	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	3,831.000	LF

Proposal:240261 **Let Date:**November 21, 2024 **Call Order:**585
J/P Num:31895(04) **Proj. Num:**STP-269B(090)PM
Counties:STEPHENS
Description:BRIDGE AND APPROACHES
SH-53: OVER WALKER CREEK,
7.1 MILES WEST OF THE SH-53/ US-81
INTERSECTION NEAR CORUM.
PROJECT LENGTH = 0.407 MILES

	Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A' NBI: 32165				
	0430	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	205.000	CY
	0440	501(G)1800	CLSM BACKFILL	208.100	CY
	0450	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	548.400	LF
	0460	504(A)5200	APPROACH SLAB	281.200	SY
	0470	504(B)5300	SAW-CUT GROOVING	760.500	SY
	0480	504(D)5420	CONCRETE RAIL (TR4)	342.200	LF
	0490	506(A)7200	STRUCTURAL STEEL	680.000	LB
	0500	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	5.000	EA
	0510	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	5.000	EA
	0520	509(A)0210	CLASS AA CONCRETE	128.200	CY
	0530	509(B)0320	CLASS A CONCRETE	99.300	CY
	0540	511(B)2310	EPOXY COATED REINFORCING STEEL	55,510.000	LB
	0550	514(A)5210	PILES, FURNISHED (HP 10X42)	238.000	LF
	0560	514(A)5220	PILES, FURNISHED (HP 12X53)	992.000	LF
	0570	514(B)5310	PILES, DRIVEN (HP 10X42)	238.000	LF
	0580	514(B)5320	PILES, DRIVEN (HP 12X53)	992.000	LF
	0590	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
	0600	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	536.000	SY
	0610	518(B)0300	SEALED EXPANSION JOINTS	41.800	LF
	0620	601(B)1230	TYPE I-A PLAIN RIPRAP	2,510.000	TON
	0630	601(C)1310	TYPE I-A FILTER BLANKET	595.000	TON
	0640	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	84.000	LF
	0650	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF
	0660	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TRAFFIC CONTROL				
	0670	853 5115	DELINEATORS(TYPE 2, CODE 1)	32.000	EA
	0680	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	5,327.000	LF
	0690	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	2,000.000	EA
	0700	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	1,250.000	EA
	0710	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	1,250.000	EA
	0720	871(B)2300	CONST.ZONE IMPACT ATTEN.	120.000	SD
	0730	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	3,115.000	LF
	0740	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,440.000	SD
	0750	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,760.000	SD
	0760	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	240.000	SD
	0770	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	600.000	SD
	0780	880(C)6420	WING BARRICADES	720.000	SD
	0790	880(E)6600	WARNING LIGHTS(TYPE A)	960.000	SD
	0800	880(F)6700	DRUMS	10,800.000	SD
	0810	880(I)7000	FLAGGER	60.000	SD
	0820	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	388.000	SD

Proposal: 240261 **Let Date:** November 21, 2024 **Call Order:** 585
J/P Num: 31895(04) **Proj. Num:** STP-269B(090)PM
Counties: STEPHENS
Description: BRIDGE AND APPROACHES
SH-53: OVER WALKER CREEK,
7.1 MILES WEST OF THE SH-53/ US-81
INTERSECTION NEAR CORUM.
PROJECT LENGTH = 0.407 MILES

Line #		Item Description	Quantity	Unit
0004	SIGNING AND STRIPING			
0830	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	3,958.000	LF
0840	855(A)7200	TRAFFIC STRIPE(PLASTIC)(4" WIDE)	7,268.000	LF
0005	STAKING			
0850	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0860	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0870	641 2110	MOBILIZATION	1.000	LSUM