**Proposal:**240263 **Let Date:**November 14, 2024 **Call Order:**080
**J/P Num:**36525(04) **Proj. Num:**IN-MC-72A
**Counties:**MCINTOSH
**Description:**BRIDGE REHABILITATION
INDIAN NATION TURNPIKE (BRIDGE NO. 15.83): OVER MILL CREEK, 4.0 MILES SOUTH OF SH-9 NEAR VERNON.
PROJECT LENGTH = 0.262 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0001** | ROADWAY | | | |
| 0005 | 202(A)2200 | UNCLASSIFIED EXCAVATION | 15.000 | CY |
| 0010 | 221(B)2300 | TEMPORARY SILT FENCE | 300.000 | LF |
| 0020 | 230(A)7200 | SOLID SLAB SODDING | 1,000.000 | SY |
| 0030 | 310(B)5300 | SUBGRADE, METHOD B | 840.000 | SY |
| 0040 | 414(A)5200 | P.C.CONCRETE PAVEMENT(PLACEMENT) | 840.000 | SY |
| 0050 | 414(G)5800 | P.C. CONCRETE FOR PAVEMENT | 210.000 | CY |
| 0060 | 501(G)1810 | CLSM BACKFILL | 55.000 | CY |
| 0065 | 509(A)0200 | CLASS AA CONCRETE | 20.000 | CY |
| 0070 | 619(B)6432 | REMOVAL OF CABLE BARRIER | 2,025.000 | LF |
| 0080 | 624(A)3200 | FENCE-STYLE WWF | 100.000 | LF |
| 0090 | 628 7100 | INSTALLATION OF CABLE BARRIER SYSTEM | 2,025.000 | LF |
| 0110 | 628(C)7400 | END ANCHORS | 2.000 | EA |
| 0120 | 877(C)4400 | RELOCATION OF PORT. LONGITUDINAL BARRIER | 650.000 | LF |
| **0002** | BRIDGE 'A' - NBI NO.16505 | | | |
| 0130 | 504(B)5300 | SAW-CUT GROOVING | 1,266.500 | SY |
| 0140 | 504(E)5520 | 42" F-SHAPED PARAPET | 274.660 | LF |
| 0150 | 506(A)7200 | STRUCTURAL STEEL | 7,465.000 | LB |
| 0160 | 506(A)7225 | STRUCTURAL STEEL M270 GRADE 50W | 171,591.000 | LB |
| 0170 | 507(A)8210 | WEATHERING STEEL FIXED BEARING ASSEMBLY | 20.000 | EA |
| 0180 | 507(B)8310 | WEATHERING STL EXP. BEARING ASSEMBLY | 40.000 | EA |
| 0190 | 509(A)0210 | CLASS AA CONCRETE | 318.240 | CY |
| 0200 | 511(B)2310 | EPOXY COATED REINFORCING STEEL | 76,789.000 | LB |
| 0210 | 515(A)7200 | WATER REPELLENT (VISUALLY INSPECTED) | 367.000 | SY |
| 0220 | 517 9110 | ELASTOMERIC COATING | 1,470.000 | SF |
| 0230 | 518(B)0310 | EXPANSION JOINT SYSTEM | 174.000 | LF |
| 0240 | 518(C)0400 | RAPID CURE JOINT SEALANT | 200.000 | LF |
| 0250 | 520(A)1200 | PREPARATION OF CRACKS, ABOVE WATER | 3.000 | LF |
| 0260 | 520(C)1400 | EPOXY RESIN, ABOVE WATER | 1.000 | GAL |
| 0270 | 521(A)2200 | PNEUMATICALLY PLACED MORTAR | 30.300 | SY |
| 0280 | 535 7100 | CORROSION INHIBITOR(SURFACE APPLIED) | 27.300 | SY |
| 0290 | 545 0110 | (PL)REPLACE BRIDGE ITEM (TYPE A) | 1.000 | LSUM |
| 0300 | 619(B)6304 | REMOVAL OF BRIDGE ITEMS | 1.000 | LSUM |

**Proposal:**240263 **Let Date:**November 14, 2024 **Call Order:**080
**J/P Num:**36525(04) **Proj. Num:**IN-MC-72A
**Counties:**MCINTOSH
**Description:**BRIDGE REHABILITATION
INDIAN NATION TURNPIKE (BRIDGE NO. 15.83): OVER MILL CREEK, 4.0 MILES SOUTH OF SH-9 NEAR VERNON.
PROJECT LENGTH = 0.262 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0003** | TRAFFIC | | | |
| 0310 | 856(A)8204 | TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE) | 17,500.000 | LF |
| 0320 | 857(A)9205 | CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE) | 9,500.000 | LF |
| 0330 | 857(F)9700 | PAVEMENT MRKNG.REMOVAL(TRAF.STRP) | 17,500.000 | LF |
| 0340 | 871(B)2300 | CONST.ZONE IMPACT ATTEN. | 520.000 | SD |
| 0350 | 877(B)4300 | DELIVER PORTABLE LONGITUDINAL BARRIER | 712.500 | LF |
| 0360 | 877(C)4400 | RELOCATION OF PORT. LONGITUDINAL BARRIER | 712.500 | LF |
| 0365 | 880(A)6220 | ARROW DISPLAY(TYPE C) | 490.000 | SD |
| 0370 | 880(B)6300 | CONSTRUCTION SIGNS 0 TO 6.25 SF | 14,560.000 | SD |
| 0380 | 880(B)6310 | CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF | 5,460.000 | SD |
| 0390 | 880(B)6320 | CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF | 8,320.000 | SD |
| 0400 | 880(C)6410 | CONSTRUCTION BARRICADES(TYPE III) | 4,420.000 | SD |
| 0410 | 880(E)6600 | WARNING LIGHTS(TYPE A) | 22,100.000 | SD |
| 0420 | 880(E)6610 | WARNING LIGHTS(TYPE C) | 37,440.000 | SD |
| 0430 | 880(F)6700 | DRUMS | 18,720.000 | SD |
| 0440 | 880(G)6805 | CHANNELIZER CONES | 18,720.000 | SD |
| 0450 | 880(L)7310 | (SP) TRAFFIC SURVEILLANCE, OHP (NON-BID) | 400.000 | HOUR |
| 0460 | 882(A)8210 | PORT.CHANGEABLE MESSAGE SIGN | 534.000 | SD |
| **0004** | STAKING | | | |
| 0470 | 642(B)3300 | CONSTRUCTION STAKING LEVEL II | 1.000 | LSUM |
| **0005** | CONSTRUCTION | | | |
| 0480 | 641 2110 | MOBILIZATION | 1.000 | LSUM |