Proposal:240286 **Let Date:**November 21, 2024 **Call Order:**501
J/P Num:31287(04) **Proj. Num:**STP-201C(065)CI
Counties:ADAIR
Description:BRIDGE AND APPROACHES
COUNTY ROAD (N 4670 ROAD): OVER BARRON FORK CREEK,
0.6 MILES SOUTH OF THE US-62 JUNCTION NEAR CHRISTIE.
PROJECT LENGTH = 0.556 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	15,462.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	32,858.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	210 0100	OBLITERATING ABANDONED ROAD	1,145.000	LF
0060	221(B)2300	TEMPORARY SILT FENCE	4,651.000	LF
0070	221(E)2600	TEMPORARY SILT DIKE	245.000	LF
0080	230(A)7200	SOLID SLAB SODDING	36,779.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	6.160	AC
0100	303(A)1200	AGGREGATE BASE TYPE A	2,226.000	CY
0110	307(K)4200	STABILIZED SUBGRADE	11,125.000	SY
0120	325 0100	SEPARATOR FABRIC	11,125.000	SY
0130	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	628.000	TON
0140	407(B)7300	TACK COAT	715.000	GAL
0150	408 8100	PRIME COAT	6,522.000	GAL
0160	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	2,234.000	TON
0170	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,091.000	TON
0180	412 3100	COLD MILLING PAVEMENT	1,904.000	SY
0190	509(D)0500	CLASS C CONCRETE	55.100	CY
0200	601(B)1220	TYPE I-A PLAIN RIPRAP	80.000	TON
0210	601(C)1300	TYPE I-A FILTER BLANKET	21.000	TON
0220	609(B)4330	1'-8" COMB.CRB.& GUT.(6" BARRIER)	261.000	LF
0230	613(A)5400	14" X 23" R.C.PIPE ELL. CLASS HE-III	80.000	LF
0240	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	97.000	LF
0250	613(EE)5973	24" CORRUGATED POLYPROPYLENE PIPE	76.000	LF
0260	613(M)6960	TYPE A4 CULVERT END TREATMENT	6.000	EA
0270	613(M)6964	TYPE B4 CULVERT END TREATMENT	2.000	EA
0280	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0290	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	3,106.000	LF
0300	624(D)3500	GATE, GALVANIZED STEEL	5.000	EA
0310	629(D)7500	REMOVE AND RESET MAILBOX	2.000	EA

Proposal:240286 **Let Date:**November 21, 2024 **Call Order:**501
J/P Num:31287(04) **Proj. Num:**STP-201C(065)CI
Counties:ADAIR
Description:BRIDGE AND APPROACHES
COUNTY ROAD (N 4670 ROAD): OVER BARRON FORK CREEK,
0.6 MILES SOUTH OF THE US-62 JUNCTION NEAR CHRISTIE.
PROJECT LENGTH = 0.556 MILES

	Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A' - NBI NO. 33248				
	0320	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	210.000	CY
	0330	501(G)1800	CLSM BACKFILL	92.000	CY
	0340	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	1,792.000	LF
	0350	504(B)5300	SAW-CUT GROOVING	1,391.600	SY
	0360	504(D)5410	CONCRETE RAIL (TR3)	961.200	LF
	0370	506(A)7200	STRUCTURAL STEEL	2,480.000	LB
	0380	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	24.000	EA
	0390	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	24.000	EA
	0400	509(A)0210	CLASS AA CONCRETE	426.600	CY
	0410	509(B)0320	CLASS A CONCRETE	176.200	CY
	0420	511(A)2210	REINFORCING STEEL	119,805.000	LB
	0430	514(A)5210	PILES, FURNISHED (HP 10X42)	100.000	LF
	0440	514(A)5220	PILES, FURNISHED (HP 12X53)	329.000	LF
	0450	514(B)5310	PILES, DRIVEN (HP 10X42)	100.000	LF
	0460	514(B)5320	PILES, DRIVEN (HP 12X53)	329.000	LF
	0470	514(K)6200	(PL)PILOT HOLES	135.000	LF
	0480	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
	0490	516(A)8225	DRILLED SHAFTS 42" DIAMETER	306.000	LF
	0500	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
	0510	517 9110	ELASTOMERIC COATING	1,325.000	SF
	0520	518(B)0300	SEALED EXPANSION JOINTS	105.510	LF
	0530	601(B)1230	TYPE I-A PLAIN RIPRAP	3,469.000	TON
	0540	601(C)1310	TYPE I-A FILTER BLANKET	572.000	TON
	0550	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	64.000	LF
	0560	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	72.000	LF
	0570	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	BRIDGE 'B' - NBI NO. 33247				
	0580	202(A)2210	UNCLASSIFIED EXCAVATION	317.000	CY
	0590	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	440.000	CY
	0600	509(A)0210	CLASS AA CONCRETE	669.900	CY
	0610	511(A)2210	REINFORCING STEEL	101,578.000	LB
	0620	601(B)1230	TYPE I-A PLAIN RIPRAP	1,133.000	TON
	0630	601(C)1310	TYPE I-A FILTER BLANKET	227.000	TON

Proposal:240286 **Let Date:**November 21, 2024 **Call Order:**501
J/P Num:31287(04) **Proj. Num:**STP-201C(065)CI
Counties:ADAIR
Description:BRIDGE AND APPROACHES
COUNTY ROAD (N 4670 ROAD): OVER BARRON FORK CREEK,
0.6 MILES SOUTH OF THE US-62 JUNCTION NEAR CHRISTIE.
PROJECT LENGTH = 0.556 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC			
0640	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	912.500	LF
0650	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0660	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0670	850(A)1200	SHEET ALUMINUM SIGNS	30.500	SF
0680	851(C)2415	2" SQUARE TUBE POST	60.000	LF
0690	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	49.000	EA
0700	856(A)8200	TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	11,748.000	LF
0710	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	42,120.000	SD
0720	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,080.000	SD
0730	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	540.000	SD
0740	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,620.000	SD
0750	880(E)6600	WARNING LIGHTS(TYPE A)	3,240.000	SD
0005	STAKING			
0760	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0770	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0780	641 2100	MOBILIZATION	1.000	LSUM