Proposal:240288 **Let Date:**November 20, 2024 **Call Order:**010
J/P Num:38661(04) **Proj. Num:**CSM-25B-S
Counties:WASHITA
Description:AIRFIELD ELECTRICAL REHABILITATION
AT CLINTON SHERMAN AIRPORT NEAR BURNS FLAT, OKLAHOMA.

Line #		Item Description	Quantity	Unit
0001	Electrical			
0010	L-108-005	Install Cable in Duct	3,080.000	LF
0020	L-108-005	Install Cable in Duct	11,590.000	LF
0030	L-108-005	Install Cable in Duct	82,230.000	LF
0040	L-108-005	Install Cable in Duct	3,080.000	LF
0050	L-108-005	Install Cable in Duct	11,590.000	LF
0060	L-108-010	Bare Counterpoise Wire	23,840.000	LF
0070	L-109-020	Furnish and Install 10 kW Constant Current Regulator	1.000	EA
0080	L-109-030	Furnish and Install 15 kW Constant Current Regulator	3.000	EA
0090	L-109-031	Furnish 15 kW Constant Current Regulator (Spare)	1.000	EA
0100	L-109-100	Vault Modifications	1.000	LSUM
0110	L-109-200	Airport Lighting Control and Monitoring System (ALCMS)	1.000	EA
0120	L-110-100	2" Electrical Duct and Trench (Native Soil)	14,870.000	LF
0130	L-110-101	2" Electrical Duct and Trench (Pavement)	6,530.000	LF
0140	L-110-200	2" PVC, Schedule 80, Bore Duct Under Pavement	600.000	LF
0150	L-110-210	3" PVC, Schedule 80, Bore Duct Under Pavement	254.000	LF
0160	L-115-100	L-867, Size B, Junction Box	34.000	EA
0170	L-125-001	L-867 Cover Plate	68.000	EA
0175	L-125-030	Furnish and Install L-849I(L), Style E, REIL System	2.000	EA
0180	L-125-050	Furnish and Install L-880(L) 4-Box PAPI System	2.000	EA
0190	L-125-100	L-862 LED Runway Edge Light on Existing Base	99.000	EA
0200	L-125-100	L-862 LED Runway Edge Light on Existing Base	36.000	EA
0210	L-125-105	L-862 LED Runway Edge Light on New Base	4.000	EA
0220	L-125-110	L-850C LED Semiflush Mounted Runway Edge Light & New Base	4.000	EA
0230	L-125-125	L-862E LED Runway Threshold Light on New Base	16.000	EA
0240	L-125-130	L-861T LED Taxiway Edge Light on Existing Base	332.000	EA
0250	L-125-135	L-861T LED Taxiway Edge Light on New Base	102.000	EA
0260	L-125-140	L-852T LED Semiflush Mounted Taxiway Edge Light	3.000	EA
0270	L-125-200	Spare L-862 LED Runway Edge Light Fixture	10.000	EA
0280	L-125-200	Spare L-862 LED Runway Edge Light Fixture	4.000	EA
0290	L-125-205	Spare L-862E LED Runway Threshold Light Fixture	2.000	EA
0300	L-125-210	Spare L-861T LED Taxiway Edge Light Fixture	44.000	EA
0310	L-125-300	Non-Lighted Guidance Sign	3.000	EA
0320	L-125-310	1 Module (LED) Lighted Guidance Sign	16.000	EA
0330	L-125-315	1 Module (LED) Lighted Distance Remaining Sign	12.000	EA
0340	L-125-320	2 Module (LED) Lighted Guidance Sign	15.000	EA
0350	L-125-330	3 Module (LED) Lighted Guidance Sign	6.000	EA
0360	L-125-340	4 Module (LED) Lighted Guidance Sign	5.000	EA
0370	P-101-025	Remove Electrical Systems	1.000	LSUM
0380	T-901-001	Site Restoration	1.000	LSUM
0002	Signing			
0390	ODOT-850(A)	Aluminum Sheet Signs	6.000	EA
0400	TEMP-001	Temporary Marking, Lighting & Barricades	1.000	LSUM
0003	Construction			
0410	C-105-001	Mobilization	1.000	LSUM