Proposal: 250010 **Let Date:** January 09, 2025 **Call Order:** 135
J/P Num: 34160(04) **Proj. Num:** ERSTP-237C(076)CI
Counties: KINGFISHER
Description: EMERGENCY RELIEF
COUNTY ROAD (EW 70): OVER UNNAMED CREEK,
2.5 MILES EAST OF US-81 NEAR DOVER.
PROJECT LENGTH = 0.189 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	1,548.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	2,819.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	850.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	168.000	LF
0070	230(A)7200	SOLID SLAB SODDING	6,837.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	1.410	AC
0090	307(K)4200	STABILIZED SUBGRADE	2,889.000	SY
0100	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	61.000	TON
0110	408 8100	PRIME COAT	1,098.000	GAL
0120	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	658.000	TON
0130	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	315.000	TON
0140	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	28.000	CY
0150	509(A)0200	CLASS AA CONCRETE	96.840	CY
0160	509(D)0500	CLASS C CONCRETE	10.000	CY
0170	511(A)2200	REINFORCING STEEL	18,601.200	LB
0180	601(A)1100	TYPE I PLAIN RIPRAP	40.000	TON
0190	613(B)5500	12" CORR. GALV. STEEL PIPE	36.000	LF
0200	613(B)5516	24" CORR. GALV. STEEL PIPE	540.000	LF
0210	613(B)5528	36" CORR. GALV. STEEL PIPE	60.000	LF
0220	613(L)6700	12" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0230	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0240	613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0250	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0260	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	2,445.000	SY
0270	619(C)6600	SAWING PAVEMENT	44.000	LF
0280	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	50.000	LF
0290	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	2.000	EA
0300	623(G)1800	GUARDRAIL END TREATMENT (GET)	2.000	EA
0310	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	1,109.000	LF
0002	TRAFFIC			
0320	853 5125	DELINEATORS(TYPE 2, CODE 3)	4.000	EA
0330	856(A)8201	(SP) TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	2,000.000	LF
0340	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	7,020.000	SD
0350	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,800.000	SD
0360	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	180.000	SD
0370	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,440.000	SD
0380	880(E)6600	WARNING LIGHTS(TYPE A)	3,600.000	SD
0003	STAKING			
0390	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal: 250010 **Let Date:** January 09, 2025 **Call Order:** 135
J/P Num: 34160(04) **Proj. Num:** ERSTP-237C(076)CI
Counties: KINGFISHER
Description: EMERGENCY RELIEF
COUNTY ROAD (EW 70): OVER UNNAMED CREEK,
2.5 MILES EAST OF US-81 NEAR DOVER.
PROJECT LENGTH = 0.189 MILES

Line #		Item Description	Quantity	Unit
0004	CONSTRUCTION			
0400	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0410	641 2110	MOBILIZATION	1.000	LSUM