Proposal: 250014 **Let Date:** January 09, 2025 **Call Order:** 160
J/P Num: 35615(04) **Proj. Num:** SSR-021N(065)SR
Counties: MURRAY
Description: RESURFACE (ASPHALT)
SH-7: FROM THE I-35 JUNCTION,
EXTEND EAST NEAR DAVIS.
PROJECT LENGTH = 2.90 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	407(A)7200	FOG SEAL	435.000	GAL
0020	411 1100	(PL)CRACK SEALING ASPHALT PAVEMENT	7,650.000	LF
0030	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	11,425.000	TON
0040	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	1,350.000	TON
0050	412 3100	COLD MILLING PAVEMENT	100,500.000	SY
0002	TRAFFIC			
0060	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	20,600.000	LF
0070	856(A)8206	(SP) TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	66,600.000	LF
0080	856(A)8210	(SP) TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE)	100.000	LF
0090	856(A)8214	(SP) TRAFFIC STRIPE(MULTI-POLY)(12" WIDE)	400.000	LF
0100	856(B)8302	(SP) TRAF.STR.(MULTI-POLY.)(SYM,WRD,ETC)	2.000	EA
0110	856(B)8306	(SP) TRAFFIC STRIPE(MULTI-POLY.)(ARROWS)	36.000	EA
0120	857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	3,300.000	LF
0130	880(A)6220	ARROW DISPLAY(TYPE C)	60.000	SD
0140	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,040.000	SD
0150	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,080.000	SD
0160	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,660.000	SD
0170	880(C)6420	WING BARRICADES	240.000	SD
0180	880(E)6600	WARNING LIGHTS(TYPE A)	3,300.000	SD
0190	880(G)6805	CHANNELIZER CONES	15,480.000	SD
0200	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	222.000	SD