Proposal: 250015 **Let Date:** January 16, 2025 **Call Order:** 165
J/P Num: 20331(13) **Proj. Num:** STP-260B(060)PM
Counties: LOGAN, PAYNE
Description: GRADE, DRAIN, AND SURFACE
SH-33: FROM 2.62 MILES WEST OF THE PAYNE COUNTY LINE,
EXTEND NORTHEAST NEAR COYLE.
PROJECT LENGTH = 2.874 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY - STP-260B(060)PM			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	14,300.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	4,703.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	24,661.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	4.000	EA
0070	221(E)2600	TEMPORARY SILT DIKE	777.000	LF
0080	230(A)7200	SOLID SLAB SODDING	49,840.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	7.460	AC
0100	241 3100	MOWING	286.850	AC
0110	242 4101	STABILIZED CONSTRUCTION EXIT	1.000	EA
0120	303(A)1200	AGGREGATE BASE TYPE A	19,761.000	CY
0130	307(K)4200	STABILIZED SUBGRADE	98,302.000	SY
0140	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	98,302.000	SY
0150	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	9,924.000	TON
0160	407(B)7300	TACK COAT	11,631.000	GAL
0170	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	10,158.000	TON
0180	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	20,446.000	TON
0190	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	14,476.000	TON
0200	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	2,250.000	TON
0210	412 3100	COLD MILLING PAVEMENT	68,810.000	SY
0220	509(D)0500	CLASS C CONCRETE	161.000	CY
0230	601(A)1100	TYPE I PLAIN RIPRAP	13.000	TON
0240	601(F)1610	TYPE IV GROUTED RIPRAP	97.000	SY
0250	611(G)0354	INLET (SMD-TYPE 2)	4.000	EA
0260	613(A)5216	24" R.C.PIPE CLASS III	342.000	LF
0270	613(B)5508	18" CORR. GALV. STEEL PIPE	508.000	LF
0280	613(B)5516	24" CORR. GALV. STEEL PIPE	48.000	LF
0290	613(H)6210	8" PERFORATED PIPE UNDERDRAIN ROUND	176.000	LF
0300	613(I)6315	8" NON-PERF.PIPE UNDERDRAIN RND.	59.000	LF
0310	613(M)6964	TYPE B4 CULVERT END TREATMENT	4.000	EA
0320	613(M)7008	TYPE B6 CULVERT END TREATMENT	2.000	EA
0330	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
0340	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0350	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	11,379.000	SY
0360	619(C)6600	SAWING PAVEMENT	3,952.000	LF
0370	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	725.000	LF
0380	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0390	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA

Proposal:250015 **Let Date:**January 16, 2025 **Call Order:**165
J/P Num:20331(13) **Proj. Num:**STP-260B(060)PM
Counties:LOGAN, PAYNE
Description:GRADE, DRAIN, AND SURFACE
SH-33: FROM 2.62 MILES WEST OF THE PAYNE COUNTY LINE,
EXTEND NORTHEAST NEAR COYLE.
PROJECT LENGTH = 2.874 MILES

Line #		Item Description	Quantity	Unit
0002	SIGNING AND STRIPING - STP-260B(060)PM			
0400	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	35,359.000	LF
0410	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	39.000	EA
0420	850(A)1200	SHEET ALUMINUM SIGNS	834.000	SF
0430	851(C)2415	2" SQUARE TUBE POST	1,384.000	LF
0440	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	22.000	EA
0450	856(A)8201	(SP) TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	4,133.000	LF
0460	856(A)8206	(SP) TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	88,713.000	LF
0470	856(A)8218	(SP) TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	96.000	LF
0480	856(B)8306	(SP) TRAFFIC STRIPE(MULTI-POLY.)(ARROWS)	39.000	EA
0490	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	17,925.000	LF
0500	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	6.000	EA
0510	857(F)9720	PAVEMENT MARKING REMOVAL(WORDS)	3.000	EA
0520	871(A)2200	IMPACT ATTENUATOR	1.000	EA
0003	TRAFFIC CONTROL - STP-260B(060)PM			
0530	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	12,860.000	LF
0540	857(E)9600	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS	2,572.000	EA
0550	871(B)2300	CONST.ZONE IMPACT ATTEN.	1,320.000	SD
0560	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,575.000	LF
0570	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,900.000	LF
0580	878(B)5300	MODULAR GLARE SCREEN (TEMPORARY)	4,800.000	SD
0590	880(A)6220	ARROW DISPLAY(TYPE C)	75.000	SD
0600	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,725.000	SD
0610	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,995.000	SD
0620	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,300.000	SD
0630	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,525.000	SD
0640	880(C)6420	WING BARRICADES	720.000	SD
0650	880(E)6600	WARNING LIGHTS(TYPE A)	1,650.000	SD
0660	880(F)6700	DRUMS	10,755.000	SD
0670	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	538.000	SD
0004	STAKING - STP-260B(060)PM			
0680	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION - STP-260B(060)PM			
0690	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0700	641 2110	MOBILIZATION	1.000	LSUM