Proposal: 250017 **Let Date:** January 16, 2025 **Call Order:** 167
J/P Num: 20331(13) **Proj. Num:** STP-260B(060)PM
20331(14) STP-260B(061)PM
Counties: LOGAN, PAYNE
Description: GRADE, DRAIN, AND SURFACE
SH-33: FROM 2.62 MILES WEST OF THE PAYNE COUNTY LINE,
EXTEND NORTHEAST NEAR COYLE.
PROJECT LENGTH = 9.605 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY - STP-260B(060)PM			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	14,300.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	4,703.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	24,661.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	4.000	EA
0070	221(E)2600	TEMPORARY SILT DIKE	777.000	LF
0080	230(A)7200	SOLID SLAB SODDING	49,840.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	7.460	AC
0100	241 3100	MOWING	286.850	AC
0110	242 4101	STABILIZED CONSTRUCTION EXIT	1.000	EA
0120	303(A)1200	AGGREGATE BASE TYPE A	19,761.000	CY
0130	307(K)4200	STABILIZED SUBGRADE	98,302.000	SY
0140	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	98,302.000	SY
0150	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	9,924.000	TON
0160	407(B)7300	TACK COAT	11,631.000	GAL
0170	411(B)1320	SUPERPAVE, TYPE S3(PG 70-28 OK)	10,158.000	TON
0180	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	20,446.000	TON
0190	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	14,476.000	TON
0200	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	2,250.000	TON
0210	412 3100	COLD MILLING PAVEMENT	68,810.000	SY
0220	509(D)0500	CLASS C CONCRETE	161.000	CY
0230	601(A)1100	TYPE I PLAIN RIPRAP	13.000	TON
0240	601(F)1610	TYPE IV GROUTED RIPRAP	97.000	SY
0250	611(G)0354	INLET (SMD-TYPE 2)	4.000	EA
0260	613(A)5216	24" R.C.PIPE CLASS III	342.000	LF
0270	613(B)5508	18" CORR. GALV. STEEL PIPE	508.000	LF
0280	613(B)5516	24" CORR. GALV. STEEL PIPE	48.000	LF
0290	613(H)6210	8" PERFORATED PIPE UNDERDRAIN ROUND	176.000	LF
0300	613(I)6315	8" NON-PERF.PIPE UNDERDRAIN RND.	59.000	LF
0310	613(M)6964	TYPE B4 CULVERT END TREATMENT	4.000	EA
0320	613(M)7008	TYPE B6 CULVERT END TREATMENT	2.000	EA
0330	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
0340	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0350	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	11,379.000	SY
0360	619(C)6600	SAWING PAVEMENT	3,952.000	LF
0370	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	725.000	LF
0380	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0390	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA

Proposal: 250017 **Let Date:** January 16, 2025 **Call Order:** 167
J/P Num: 20331(13) **Proj. Num:** STP-260B(060)PM
20331(14) STP-260B(061)PM
Counties: LOGAN, PAYNE
Description: GRADE, DRAIN, AND SURFACE
SH-33: FROM 2.62 MILES WEST OF THE PAYNE COUNTY LINE, EXTEND NORTHEAST NEAR COYLE.
PROJECT LENGTH = 9.605 MILES

	Line #		Item Description	Quantity	Unit
0002	SIGNING AND STRIPING - STP-260B(060)PM				
	0400	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	35,359.000	LF
	0410	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	39.000	EA
	0420	850(A)1200	SHEET ALUMINUM SIGNS	834.000	SF
	0430	851(C)2415	2" SQUARE TUBE POST	1,384.000	LF
	0440	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	22.000	EA
	0450	856(A)8201	(SP) TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	4,133.000	LF
	0460	856(A)8206	(SP) TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	88,713.000	LF
	0470	856(A)8218	(SP) TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	96.000	LF
	0480	856(B)8306	(SP) TRAFFIC STRIPE(MULTI-POLY.)(ARROWS)	39.000	EA
	0490	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	17,925.000	LF
	0500	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	6.000	EA
	0510	857(F)9720	PAVEMENT MARKING REMOVAL(WORDS)	3.000	EA
	0520	871(A)2200	IMPACT ATTENUATOR	1.000	EA
0003	TRAFFIC CONTROL - STP-260B(060)PM				
	0530	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	12,860.000	LF
	0540	857(E)9600	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS	2,572.000	EA
	0550	871(B)2300	CONST.ZONE IMPACT ATTEN.	1,320.000	SD
	0560	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,575.000	LF
	0570	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,900.000	LF
	0580	878(B)5300	MODULAR GLARE SCREEN (TEMPORARY)	4,800.000	SD
	0590	880(A)6220	ARROW DISPLAY(TYPE C)	75.000	SD
	0600	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,725.000	SD
	0610	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,995.000	SD
	0620	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,300.000	SD
	0630	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,525.000	SD
	0640	880(C)6420	WING BARRICADES	720.000	SD
	0650	880(E)6600	WARNING LIGHTS(TYPE A)	1,650.000	SD
	0660	880(F)6700	DRUMS	10,755.000	SD
	0670	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	538.000	SD

Proposal: 250017 **Let Date:** January 16, 2025 **Call Order:** 167
J/P Num: 20331(13) **Proj. Num:** STP-260B(060)PM
20331(14) STP-260B(061)PM
Counties: LOGAN, PAYNE
Description: GRADE, DRAIN, AND SURFACE
SH-33: FROM 2.62 MILES WEST OF THE PAYNE COUNTY LINE,
EXTEND NORTHEAST NEAR COYLE.
PROJECT LENGTH = 9.605 MILES

Line #		Item Description	Quantity	Unit
0004	ROADWAY - STP-260B(061)PM			
0680	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0690	202(A)2200	UNCLASSIFIED EXCAVATION	41,296.000	CY
0700	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0710	221(B)2300	TEMPORARY SILT FENCE	63,053.000	LF
0720	221(C)2400	TEMPORARY SEDIMENT FILTER	26.000	EA
0730	221(E)2600	TEMPORARY SILT DIKE	945.000	LF
0740	230(A)7200	SOLID SLAB SODDING	128,181.000	SY
0750	233(A)0200	VEGETATIVE MULCHING	17.400	AC
0760	241 3100	MOWING	513.260	AC
0770	242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0780	303(A)1200	AGGREGATE BASE TYPE A	49,099.000	CY
0790	307(K)4200	STABILIZED SUBGRADE	236,012.000	SY
0800	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	236,787.000	SY
0810	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	28,895.000	TON
0820	407(B)7300	TACK COAT	544.000	GAL
0830	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	48,090.000	TON
0840	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	804.000	TON
0850	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	35,677.000	SY
0860	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	145,062.000	SY
0870	414(G)5800	P.C. CONCRETE FOR PAVEMENT	40,065.000	CY
0880	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	34.000	CY
0890	509(A)0200	CLASS AA CONCRETE	61.000	CY
0900	509(D)0500	CLASS C CONCRETE	246.000	CY
0910	511(A)2200	REINFORCING STEEL	8,431.000	LB
0920	601(A)1100	TYPE I PLAIN RIPRAP	4.000	TON
0930	601(F)1610	TYPE IV GROUTED RIPRAP	1,475.000	SY
0940	611(G)0354	INLET (SMD-TYPE 2)	4.000	EA
0950	613(A)5216	24" R.C.PIPE CLASS III	390.000	LF
0960	613(B)5508	18" CORR. GALV. STEEL PIPE	1,080.000	LF
0970	613(B)5516	24" CORR. GALV. STEEL PIPE	62.000	LF
0980	613(H)6210	8" PERFORATED PIPE UNDERDRAIN ROUND	339.000	LF
0990	613(I)6315	8" NON-PERF.PIPE UNDERDRAIN RND.	113.000	LF
1000	613(M)6964	TYPE B4 CULVERT END TREATMENT	3.000	EA
1010	613(M)7008	TYPE B6 CULVERT END TREATMENT	3.000	EA
1020	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
1030	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
1040	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	22,626.000	SY
1050	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	195.000	SY
1060	619(C)6600	SAWING PAVEMENT	4,960.000	LF
1070	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	513.000	LF
1080	623(G)1800	GUARDRAIL END TREATMENT (GET)	3.000	EA
1090	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	3.000	EA

Proposal: 250017 **Let Date:** January 16, 2025 **Call Order:** 167
J/P Num: 20331(13) **Proj. Num:** STP-260B(060)PM
20331(14) STP-260B(061)PM
Counties: LOGAN, PAYNE
Description: GRADE, DRAIN, AND SURFACE
SH-33: FROM 2.62 MILES WEST OF THE PAYNE COUNTY LINE, EXTEND NORTHEAST NEAR COYLE.
PROJECT LENGTH = 9.605 MILES

	Line #		Item Description	Quantity	Unit
0005	SIGNING AND STRIPING - STP-260B(061)PM				
	1100	413(C)4400	RUMBLE STRIP-METHOD PCC-CON	80,086.000	LF
	1110	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	10.000	EA
	1120	850(A)1200	SHEET ALUMINUM SIGNS	1,357.000	SF
	1130	851(C)2415	2" SQUARE TUBE POST	2,253.000	LF
	1140	856(A)8206	(SP) TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	37,100.000	LF
	1150	856(B)8306	(SP) TRAFFIC STRIPE(MULTI-POLY.)(ARROWS)	46.000	EA
	1160	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	80,278.000	LF
	1170	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	2.000	EA
	1180	871(A)2200	IMPACT ATTENUATOR	1.000	EA
0006	TRAFFIC CONTROL - STP-260B(061)PM				
	1190	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	118,539.000	LF
	1200	857(E)9600	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS	34,904.000	EA
	1210	871(B)2300	CONST.ZONE IMPACT ATTEN.	3,130.000	SD
	1220	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,650.000	LF
	1230	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	3,290.000	LF
	1240	878(B)5300	MODULAR GLARE SCREEN (TEMPORARY)	36,580.000	SD
	1250	880(A)6220	ARROW DISPLAY(TYPE C)	620.000	SD
	1260	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	11,160.000	SD
	1270	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,480.000	SD
	1280	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	8,060.000	SD
	1290	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	4,960.000	SD
	1300	880(C)6420	WING BARRICADES	1,240.000	SD
	1310	880(E)6600	WARNING LIGHTS(TYPE A)	3,720.000	SD
	1320	880(F)6700	DRUMS	42,000.000	SD
	1330	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	908.000	SD
0007	STAKING - STP-260B(061)PM				
	1340	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008	CONSTRUCTION - STP-260B(061)PM				
	1350	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1360	641 2110	MOBILIZATION	1.000	LSUM