Proposal: 250019 **Let Date:** January 09, 2025 **Call Order:** 175
J/P Num: 35648(04) **Proj. Num:** SSR-012N(114)SR
Counties: POTTAWATOMIE
Description: RESURFACE (ASPHALT)
SH-99: FROM 0.1 MILES NORTH OF THE SEMINOLE COUNTY LINE, EXTEND NORTH NEAR PRAGUE.
PROJECT LENGTH = 5.81 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	407(B)7300	TACK COAT	6,430.000	GAL
0020	411(D)1520	SUPERPAVE, TYPE S5(PG 70-28 OK)	6,650.000	TON
0030	412 3100	COLD MILLING PAVEMENT	75,594.000	SY
0002	TRAFFIC			
0040	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	19,785.000	LF
0050	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	39,570.000	LF
0060	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	96,572.000	LF
0070	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	1,188.000	LF
0080	856(B)8306	(SP) TRAFFIC STRIPE(MULTI-POLY.)(ARROWS)	18.000	EA
0090	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,369.000	SD
0100	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	296.000	SD
0110	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	481.000	SD
0120	880(E)6607	WARNING LIGHTS(TYPE B)	1,369.000	SD
0130	880(I)7000	FLAGGER	23.000	SD
0140	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	88.000	SD