Proposal: 250021 **Let Date:** January 09, 2025 **Call Order:** 185
J/P Num: 35080(04) **Proj. Num:** SSR-268C(101)SR
Counties: SEQUOYAH
Description: RESURFACE (ASPHALT)
SH-64B: FROM 5.39 MILES NORTH OF THE I-40 JUNCTION, EXTEND NORTH NEAR MULDROW.
PROJECT LENGTH = 5.87 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	407(B)7300	TACK COAT	6,440.000	GAL
0020	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	8,486.000	TON
0030	412 3100	COLD MILLING PAVEMENT	75,761.000	SY
0040	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	30,993.000	LF
0002	TRAFFIC			
0050	856(A)8201	(SP) TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	118,357.000	LF
0060	856(A)8218	(SP) TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	11.000	LF
0070	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	780.000	SD
0080	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	630.000	SD
0090	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,080.000	SD
0100	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	300.000	SD
0110	880(C)6420	WING BARRICADES	150.000	SD
0120	880(E)6600	WARNING LIGHTS(TYPE A)	450.000	SD
0130	880(F)6700	DRUMS	1,020.000	SD
0140	880(G)6805	CHANNELIZER CONES	4,860.000	SD
0150	880(I)7000	FLAGGER	60.000	SD
0160	880(W)7700	PILOT CAR	1.000	LSUM