Proposal:250030 **Let Date:**January 09, 2025 **Call Order:**225
J/P Num:35683(04) **Proj. Num:**SSR-252C(122)SR
Counties:NOBLE
Description:RESURFACE (ASPHALT)
US-77: FROM 3.6 MILES SOUTH OF
US-412, EXTEND NORTH NEAR PERRY.
PROJECT LENGTH = 8.000 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(D)2520	UNCLASSIFIED BORROW (TOPSOIL)	4,000.000	CY
0020	303(A)1200	AGGREGATE BASE TYPE A	500.000	CY
0030	407(C)7500	NT TACK MATERIAL	22,500.000	GAL
0040	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	12,000.000	TON
0050	411(D)1530	SUPERPAVE, TYPE S5(PG 64-22 OK)	4,200.000	TON
0060	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	1,500.000	TON
0070	412 3100	COLD MILLING PAVEMENT	23,500.000	SY
0080	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	42,000.000	LF
0090	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,567.000	SY
0100	619(B)6376	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	1,200.000	SY
0110	619(C)6600	SAWING PAVEMENT	4,440.000	LF
0002	TRAFFIC			
0120	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	147,000.000	LF
0130	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	500.000	LF
0140	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	24.000	LF
0150	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	8.000	EA
0160	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	9,000.000	EA
0170	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	5,000.000	LF
0180	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,000.000	SD
0190	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,000.000	SD
0200	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,000.000	SD
0210	880(B)6330	CONSTRUCTION SIGNS 33.0 SF & OVER	480.000	SD
0220	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	120.000	SD
0230	880(E)6607	WARNING LIGHTS(TYPE B)	3,000.000	SD
0240	880(F)6700	DRUMS	5,000.000	SD
0250	880(G)6805	CHANNELIZER CONES	5,000.000	SD
0260	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	500.000	HOUR
0270	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	240.000	SD
0003	CONSTRUCTION			
0280	641 2110	MOBILIZATION	1.000	LSUM