Proposal: 250033 **Let Date:** January 09, 2025 **Call Order:** 240
J/P Num: 35137(04) **Proj. Num:** SBR-253C(069)SB
Counties: NOWATA
Description: BRIDGE REHABILITATION
SH-28: OVER PANTHER CREEK, 5.6 MILES
SOUTH OF THE INTERSECTION OF US-60
NEAR NEW ALLUWE.
PROJECT LENGTH = 0.126 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	221(B)2300	TEMPORARY SILT FENCE	1,000.000	LF
0030	230(A)7200	SOLID SLAB SODDING	1,000.000	SY
0040	233(A)0200	VEGETATIVE MULCHING	0.500	AC
0050	407(B)7300	TACK COAT	168.000	GAL
0060	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	315.000	TON
0070	412 3100	COLD MILLING PAVEMENT	2,093.000	SY
0080	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	93.000	SY
0090	619(B)6396	REMOVAL OF GUARDRAIL	565.000	LF
0100	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	450.000	LF
0110	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0120	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0130	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	20.000	EA
0002	BRIDGE "A" - NBI 15096 - SH-28 OVER PANTHER CREEK			
0140	202(A)2210	UNCLASSIFIED EXCAVATION	30.000	CY
0150	501(G)1800	CLSM BACKFILL	90.000	CY
0160	502(B)3310	FALSEWORK AND JACKING	1.000	LSUM
0170	504(A)5200	APPROACH SLAB	217.800	SY
0180	504(B)5300	SAW-CUT GROOVING	650.300	SY
0190	504(D)5420	CONCRETE RAIL (TR4)	383.800	LF
0200	506(A)7200	STRUCTURAL STEEL	3,000.000	LB
0210	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	12.000	EA
0220	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	12.000	EA
0230	509(A)0210	CLASS AA CONCRETE	139.400	CY
0240	509(B)0320	CLASS A CONCRETE	7.000	CY
0250	511(B)2310	EPOXY COATED REINFORCING STEEL	40,320.000	LB
0260	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0270	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0280	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	361.200	SY
0290	517 9110	ELASTOMERIC COATING	548.000	SF
0300	518(B)0300	SEALED EXPANSION JOINTS	66.000	LF
0310	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	126.000	LF
0320	520(C)1400	EPOXY RESIN, ABOVE WATER	2.000	GAL
0330	521(A)2200	PNEUMATICALLY PLACED MORTAR	44.000	SY
0340	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	82.000	SY
0350	601(B)1230	TYPE I-A PLAIN RIPRAP	46.000	TON
0360	601(I)1700	FILTER FABRIC (RIPRAP)	40.000	SY
0370	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:250033 **Let Date:**January 09, 2025 **Call Order:**240
J/P Num:35137(04) **Proj. Num:**SBR-253C(069)SB
Counties:NOWATA
Description:BRIDGE REHABILITATION
SH-28: OVER PANTHER CREEK, 5.6 MILES
SOUTH OF THE INTERSECTION OF US-60
NEAR NEW ALLUWE.
PROJECT LENGTH = 0.126 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0380	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	17,520.000	SD
0390	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,800.000	SD
0400	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	480.000	SD
0410	880(B)6330	CONSTRUCTION SIGNS 33.0 SF & OVER	240.000	SD
0420	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	960.000	SD
0430	880(E)6607	WARNING LIGHTS(TYPE B)	2,640.000	SD
0440	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	268.000	SD
0004	SIGNING AND STRIPING			
0450	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	940.000	LF
0460	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	4.000	EA
0470	850(A)1200	SHEET ALUMINUM SIGNS	37.500	SF
0480	851(C)2430	2 1/2" SQUARE TUBE POST	72.000	LF
0490	856(A)8206	(SP) TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	2,656.000	LF
0005	STAKING			
0500	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0510	641 2100	MOBILIZATION	1.000	LSUM