Proposal:250034 **Let Date:**January 16, 2025 **Call Order:**250
J/P Num:33565(04) **Proj. Num:**STP-258D(112)CI
Counties:OTTAWA
Description:WIDEN AND RESURFACE
COUNTY ROAD (E140): FROM
0.85 MILES EAST OF THE INTERSECTION
OF US-59, EXTEND NORTH AND EAST NEAR MIAMI.
PROJECT LENGTH = 2.604 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	24,471.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	5,856.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	2,457.000	LF
0060	221(G)2800	TEMPORARY FIBER LOG	48.000	LF
0070	230(A)7200	SOLID SLAB SODDING	55,383.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	11.490	AC
0090	303(A)1200	AGGREGATE BASE TYPE A	12,597.000	CY
0100	310(B)5300	SUBGRADE, METHOD B	65,476.000	SY
0110	403(A)3200	CHIP SEAL (SINGLE TREATMENT)	34,245.000	SY
0120	407(B)7300	TACK COAT	2,582.000	GAL
0130	408 8100	PRIME COAT	34,533.000	GAL
0140	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	8,164.000	TON
0150	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,589.000	TON
0160	412 3100	COLD MILLING PAVEMENT	15,765.000	SY
0170	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	86.000	CY
0180	508 9120	PRECAST REINFORCED CONCRETE BOX	46.000	LF
0190	509(A)0200	CLASS AA CONCRETE	20.000	CY
0200	509(B)0300	CLASS A CONCRETE	830.000	CY
0210	509(D)0500	CLASS C CONCRETE	10.000	CY
0220	511(A)2200	REINFORCING STEEL	2,800.000	LB
0230	611(G)0350	INLET (SMD-TYPE 1)	2.000	EA
0240	613(A)5264	18" R.C.PIPE CLASS IV	705.000	LF
0250	613(A)5268	24" R.C.PIPE CLASS IV	158.000	LF
0260	613(A)5366	36" X 22" R.C.PIPE ARCH CLASS A-III	77.000	LF
0270	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	98.000	LF
0280	613(A)5400	14" X 23" R.C.PIPE ELL. CLASS HE-III	450.000	LF
0290	613(A)5448	51" X 31" R.C.PIPE ARCH CLASS A-IV	35.000	LF
0300	613(L)6636	36" X 22" PREFAB. CULVERT END SEC., ARCH	4.000	EA
0310	613(L)6648	43" X 26" PREFAB. CULVERT END SEC., ARCH	6.000	EA
0320	613(L)6656	51" X 31" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0330	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0340	613(M)6960	TYPE A4 CULVERT END TREATMENT	38.000	EA
0350	613(M)6964	TYPE B4 CULVERT END TREATMENT	3.000	EA
0360	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0370	619(C)6600	SAWING PAVEMENT	2,195.000	LF
0380	629(D)7500	REMOVE AND RESET MAILBOX	18.000	EA

Proposal:250034 **Let Date:**January 16, 2025 **Call Order:**250
J/P Num:33565(04) **Proj. Num:**STP-258D(112)CI
Counties:OTTAWA
Description:WIDEN AND RESURFACE
COUNTY ROAD (E140): FROM
0.85 MILES EAST OF THE INTERSECTION
OF US-59, EXTEND NORTH AND EAST NEAR MIAMI.
PROJECT LENGTH = 2.604 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC			
0390	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	5.000	EA
0400	850(A)1200	SHEET ALUMINUM SIGNS	375.000	SF
0410	851(C)2420	2 1/4" SQUARE TUBE POST	600.000	LF
0420	851(C)2430	2 1/2" SQUARE TUBE POST	180.000	LF
0430	856(A)8201	(SP) TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	61,882.000	LF
0440	856(B)8310	(SP) TRAFFIC STRIPE(MULTI-POLY.)(SYMBOLS)	28.000	EA
0450	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	11,700.000	SD
0460	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	8,400.000	SD
0470	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,000.000	SD
0480	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	8,400.000	SD
0490	880(E)6600	WARNING LIGHTS(TYPE A)	16,800.000	SD
0500	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	600.000	SD
0003	STAKING			
0510	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0520	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0530	641 2110	MOBILIZATION	1.000	LSUM