Proposal: 250036 **Let Date:** January 16, 2025 **Call Order:** 260
J/P Num: 29324(04) **Proj. Num:** STP-266C(090)IG
Counties: ROGERS
Description: WIDEN AND RESURFACE
CITY STREET (N 161ST E AVENUE): FROM THE
INTERSECTION OF I-44, EXTEND NORTH IN CATOOSA.
PROJECT LENGTH = 0.937 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	9,236.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	7,367.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	448.000	LF
0060	230(A)7200	SOLID SLAB SODDING	7,530.000	SY
0070	233(A)0200	VEGETATIVE MULCHING	2.530	AC
0080	303(A)1200	AGGREGATE BASE TYPE A	1,892.000	CY
0090	310(B)5300	SUBGRADE, METHOD B	8,512.000	SY
0100	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	8,370.000	SY
0110	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	500.000	TON
0120	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	3,411.000	TON
0130	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	3,052.000	TON
0140	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	143.000	TON
0150	411(I)2000	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	3.000	TON
0160	412 3100	COLD MILLING PAVEMENT	13,089.030	SY
0170	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	514.000	CY
0180	501(G)1810	CLSM BACKFILL	500.000	CY
0190	509(A)0200	CLASS AA CONCRETE	82.000	CY
0200	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	5.660	CY
0210	509(D)0500	CLASS C CONCRETE	58.000	CY
0220	511(A)2200	REINFORCING STEEL	12,889.000	LB
0230	601(F)1610	TYPE IV GROUTED RIPRAP	138.000	SY
0240	609(B)4315	COMBINED CURB & GUTTER(8" BARRIER)	9,788.000	LF
0250	610(B)5320	8" CONCRETE DRIVEWAY	2,152.000	SY
0260	611(G)8000	INLET CDI RCB DES. 1	1.000	EA
0270	611(G)8004	INLET CDI RCB DES. 2	4.000	EA
0280	611(L)1600	JUNCTION BOXES	152.950	CF
0290	613(A)5400	14" X 23" R.C.PIPE ELL. CLASS HE-III	55.000	LF
0300	613(A)5404	19" X 30" R.C.PIPE ELL. CLASS HE-III	102.000	LF
0310	613(A)5408	24" X 38" R.C.PIPE ELL. CLASS HE-III	144.000	LF
0320	613(A)5424	43" X 68" R.C.PIPE ELL. CLASS HE-III	68.000	LF
0330	613(EE)5965	15" CORRUGATED POLYPROPYLENE PIPE	127.000	LF
0340	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	500.000	LF
0350	613(EE)5973	24" CORRUGATED POLYPROPYLENE PIPE	112.000	LF
0360	613(EE)5977	30" CORRUGATED POLYPROPYLENE PIPE	61.000	LF
0370	613(EE)5981	36" CORRUGATED POLYPROPYLENE PIPE	143.000	LF
0380	613(L)6704	15" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0390	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	18.000	EA
0400	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0410	613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	5.000	EA
0420	613(L)6800	14" X 23" PREFAB. CULVERT END SEC., ELLI	1.000	EA
0430	613(L)6804	19" X 30" PREFAB. CULVERT END SEC., ELLI	2.000	EA
0440	613(L)6808	24" X 38" PREFAB. CULVERT END SEC., ELLI	4.000	EA
0450	613(L)6824	43" X 68" PREFAB. CULVERT END SEC., ELLI	2.000	EA
0460	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM

Proposal:250036 **Let Date:**January 16, 2025 **Call Order:**260
J/P Num:29324(04) **Proj. Num:**STP-266C(090)IG
Counties:ROGERS
Description:WIDEN AND RESURFACE
CITY STREET (N 161ST E AVENUE): FROM THE
INTERSECTION OF I-44, EXTEND NORTH IN CATOOSA.
PROJECT LENGTH = 0.937 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	619(B)6300	REMOVAL OF HEADWALL	2.000	EA
0480	619(B)6356	REMOVAL OF CURB AND GUTTER	54.050	LF
0490	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	2,497.720	SY
0500	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	2,032.720	SY
0510	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	2,702.610	SY
0002	TRAFFIC			
0520	805(A)3200	REMOVAL OF SIGN FOOTING	28.000	EA
0530	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	22.000	EA
0540	850(A)1200	SHEET ALUMINUM SIGNS	144.840	SF
0550	851(C)2415	2" SQUARE TUBE POST	424.000	LF
0560	855(A)7201	(SP) TRAFFIC STRIPE(PLASTIC)(4" WIDE)	11,932.000	LF
0570	855(A)7209	(SP) TRAFFIC STRIPE(PLASTIC)(8" WIDE)	75.000	LF
0580	855(A)7217	(SP) TRAFFIC STRIPE(PLASTIC)(24" WIDE)	43.000	LF
0590	855(B)7313	(SP) TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	27.000	EA
0600	871(B)2300	CONST.ZONE IMPACT ATTEN.	20.000	SD
0610	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	276.000	LF
0620	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	426.000	LF
0630	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	7,600.000	SD
0640	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	960.000	SD
0650	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,080.000	SD
0660	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	9,280.000	SD
0670	880(E)6600	WARNING LIGHTS(TYPE A)	19,440.000	SD
0690	880(F)6700	DRUMS	36,920.000	SD
0700	880(I)7000	FLAGGER	10.000	SD
0710	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	200.000	SD
0003	STAKING			
0720	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0730	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0740	641 2110	MOBILIZATION	1.000	LSUM