Proposal:250037 **Let Date:**January 16, 2025 **Call Order:**265
J/P Num:35843(04) **Proj. Num:**NHPP-017N(309)AD
Counties:TEXAS
Description:PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
US-64: FROM THE TIGER BOULEVARD INTERSECTION,
EXTEND NORTH IN THE CITY OF GUYMON.
PROJECT LENGTH = 0.914 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	100.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	100.000	CY
0030	221(B)2300	TEMPORARY SILT FENCE	500.000	LF
0040	221(G)2800	TEMPORARY FIBER LOG	100.000	LF
0050	230(A)7200	SOLID SLAB SODDING	774.500	SY
0060	325 0100	SEPARATOR FABRIC	100.000	SY
0070	326(B)1300	GEOGRID REINFORCEMENT	100.000	SY
0080	411(I)2000	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	9.500	TON
0090	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	86.200	SY
0100	414(F)5700	PARTIAL DEPTH P.C.C. PATCH (PLACEMENT)	56.400	SY
0110	609(B)4315	COMBINED CURB & GUTTER(8" BARRIER)	85.600	LF
0120	610(A)5210	5" CONCRETE SIDEWALK	961.000	SY
0130	610(B)5320	8" CONCRETE DRIVEWAY	887.400	SY
0140	610(I)6000	TACTILE WARNING DEVICE-NEW	204.500	SF
0150	612(A)3201	(PL) MANHOLES ADJUST TO GRADE	1.000	EA
0160	612(E)3600	VALVE BOXES ADJUST TO GRADE	3.000	EA
0170	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0180	619(B)6356	REMOVAL OF CURB AND GUTTER	31.600	LF
0190	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	695.000	SY
0200	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	274.000	SY
0210	619(B)6404	REMOVAL OF SIDEWALK	140.900	SY
0002	TRAFFIC			
0220	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	7.000	EA
0230	805(B)3300	(PL)RESET OF PULL BOX	1.000	EA
0240	850(A)1200	SHEET ALUMINUM SIGNS	78.900	SF
0250	851(C)2415	2" SQUARE TUBE POST	84.000	LF
0260	856(A)8218	(SP) TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	380.000	LF
0270	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	83.300	LF
0280	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	360.000	SD
0290	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	240.000	SD
0300	880(E)6600	WARNING LIGHTS(TYPE A)	1,800.000	SD
0310	880(F)6700	DRUMS	1,800.000	SD
0320	880(G)6805	CHANNELIZER CONES	6,000.000	SD

Proposal:250037 **Let Date:**January 16, 2025 **Call Order:**265
J/P Num:35843(04) **Proj. Num:**NHPP-017N(309)AD
Counties:TEXAS
Description:PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
US-64: FROM THE TIGER BOULEVARD INTERSECTION,
EXTEND NORTH IN THE CITY OF GUYMON.
PROJECT LENGTH = 0.914 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0330	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	50.000	LF
0340	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	100.000	LF
0350	802(C)0435	3" HIGH DENSITY PE PIPE - BORED	100.000	LF
0360	803(A)1210	PULL BOX(SIZE I)	2.000	EA
0370	803(A)1220	PULL BOX(SIZE II)	1.000	EA
0380	804(A)2200	STRUCTURAL CONCRETE	2.200	CY
0390	804(B)2300	REINFORCING STEEL	210.000	LB
0400	805(A)3208	REMOVAL OF PULL BOX	3.000	EA
0410	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0420	806(B)4412	12' MTG.HT.TS PED.POLE(G.STL.)	4.000	EA
0430	811 9130	1/C NO.10 ELECT.COND.	100.000	LF
0440	830 2100	PEDESTRIAN PUSH BUTTON	4.000	EA
0450	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	4.000	EA
0460	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,100.000	LF
0470	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	100.000	LF
0480	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	100.000	LF
0490	834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	20.000	LF
0500	890 1100	(PL)TRAFFIC ITEMS	1.000	LSUM
0004	STAKING			
0510	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0520	641 2110	MOBILIZATION	1.000	LSUM