Proposal: 250038 **Let Date:** January 09, 2025 **Call Order:** 270
J/P Num: 38519(04) **Proj. Num:** SSR-271F(086)SR
Counties: TILLMAN
Description: RESURFACE (ASPHALT)
SH-5: FROM 6.3 MILES WEST OF THE INTERSECTION OF US-183, EXTEND EAST NEAR FREDRICK.
PROJECT LENGTH = 6.906 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	407(A)7200	FOG SEAL	41.000	GAL
0020	407(C)7400	(SP) POLYMER MOD. CATIONIC RAPID SET - 1S	27,485.000	GAL
0030	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	16,638.000	TON
0040	412 3100	COLD MILLING PAVEMENT	31,708.000	SY
0050	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	28,500.000	LF
0060	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	56,000.000	LF
0002	TRAFFIC SIGNING AND STRIPING			
0080	828(B)0300	LOOP DETECTOR WIRE	2,704.000	LF
0090	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	113,000.000	LF
0100	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	2,300.000	LF
0110	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	300.000	LF
0120	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	12.000	EA
0130	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	4.000	EA
0140	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	130.000	LF
0003	TRAFFIC CONTROL			
0150	104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	10.000	DAY
0160	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	6,823.000	EA
0170	880(J)7100	(SP) CONSTRUCTION TRAFFIC CONTROL	45.000	SD
0180	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	118.000	SD