Proposal:250039 **Let Date:**January 16, 2025 **Call Order:**206
J/P Num:36593(04) **Proj. Num:**STP-219N(131)IG
Counties:CREEK
Description:SAFETY IMPROVEMENT (STREETSCAPE)
CITY STREET (DEWEY AVENUE/SH-66): FROM MAIN STREET, EXTEND EAST IN THE CITY OF SAPULPA.
PROJECT LENGTH = 0.3293 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(B)1300	SELECTIVE CLEARING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	2,425.000	CY
0030	221(H)2910	INLET PROTECTION	576.000	LF
0040	242 4101	STABILIZED CONSTRUCTION EXIT	1.000	EA
0050	303(A)1200	AGGREGATE BASE TYPE A	1,447.000	CY
0060	307(K)4200	STABILIZED SUBGRADE	9,561.000	SY
0070	325 0100	SEPARATOR FABRIC	10,990.000	SY
0080	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	2,718.000	SY
0090	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	3,570.000	SY
0100	414(C)5400	CONT.REINF.P.C.C. PAVT.(PLACEMENT)	1,334.000	SY
0110	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	90.000	SY
0120	414(G)5800	P.C. CONCRETE FOR PAVEMENT	1,909.000	CY
0130	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	3,874.000	LF
0140	609(B)4335	1'-8" COMB.CRB.& GUT.(6" MNTBLE)	1,524.000	LF
0150	610(A)5200	4" CONCRETE SIDEWALK	2,344.000	SY
0160	610(I)6000	TACTILE WARNING DEVICE-NEW	242.000	SF
0170	610(J)6120	(PL) LANDSCAPE PAVERS, TYPE 1	3,092.000	SF
0180	610(J)6130	(PL) LANDSCAPE PAVERS, TYPE 2	5,397.000	SF
0190	610(J)6140	(PL) LANDSCAPE PAVERS, TYPE 3	7,749.000	SF
0200	611(A)7251	(PL) PRECAST CONC RND 4' DIA MANHOLE	2.000	EA
0210	611(A)7256	(PL) PRECAST CONC RND 5' DIA MANHOLE	5.000	EA
0220	611(A)7261	(PL) PRECAST CONC RND 6' DIA MANHOLE	3.000	EA
0230	611(B)7246	(PL) ADD'L DEPTH PRECAST RND 5' MANHOLE	7.100	VF
0240	611(B)7251	(PL) ADD'L DEPTH PRECAST RND 6' MANHOLE	7.600	VF
0250	611(G)7754	INLET CI DES. 2 (STD)	15.000	EA
0260	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	10.700	VF
0270	611(N)1850	SPECIAL WELDED STEEL GRATE	4.000	EA
0280	612(A)3201	(PL) MANHOLES ADJUST TO GRADE	2.000	EA
0290	613(EE)5965	15" CORRUGATED POLYPROPYLENE PIPE	269.000	LF
0300	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	66.000	LF
0310	613(EE)5973	24" CORRUGATED POLYPROPYLENE PIPE	55.000	LF
0320	613(EE)5977	30" CORRUGATED POLYPROPYLENE PIPE	757.000	LF
0330	613(S)7700	STANDARD BEDDING MATERIAL, CLASS B	873.000	CY
0340	613(V)8000	TRENCH EXCAVATION	1,092.000	CY
0350	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0360	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	650.000	SY
0370	619(B)6368	REMOVAL OF DRAINAGE INLETS	14.000	EA
0380	619(B)6376	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	9,760.000	SY
0390	619(B)6404	REMOVAL OF SIDEWALK	2,155.000	SY
0400	619(B)6440	REMOVAL OF EXISTING PIPE	1,403.000	LF
0410	631(A)9210	(SP)REMOVABLE BOLLARD	37.000	EA
0002	LANDSCAPING			
0420	231(A)8200	TREES	22.000	EA
0430	231(E)8600	(PL) LANDSCAPING	1.000	LSUM
0440	616 2110	(PL) IRRIGATION SYSTEM	1.000	LSUM

Proposal:250039 **Let Date:**January 16, 2025 **Call Order:**206
J/P Num:36593(04) **Proj. Num:**STP-219N(131)IG
Counties:CREEK
Description:SAFETY IMPROVEMENT (STREETSCAPE)
CITY STREET (DEWEY AVENUE/SH-66): FROM MAIN STREET, EXTEND EAST IN THE CITY OF SAPULPA.
PROJECT LENGTH = 0.3293 MILES

Line #		Item Description	Quantity	Unit
0003	MISCELLANEOUS			
0450	632 0100	(PL) SITESCAPING	1.000	LSUM
0460	804(A)2200	STRUCTURAL CONCRETE	360.000	CY
0470	804(B)2300	REINFORCING STEEL	15,540.000	LB
0480	809 7110	ENHANCEMENT LIGHTING (COMPLETE)	1.000	LSUM
0004	TRAFFIC			
0490	802(B)0340	4" PVC SCH.40 PLASTIC CONDUIT TRENCHED	3,027.000	LF
0500	803(A)1200	PULL BOX	32.000	EA
0510	805(A)3228	(PL)REMOVAL OF LIGHT POLE	15.000	EA
0520	805(A)3248	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
0530	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0540	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	6.000	EA
0550	850(A)1200	SHEET ALUMINUM SIGNS	93.000	SF
0560	851(C)2410	1 3/4" SQUARE TUBE POST	147.000	LF
0570	851(C)2415	2" SQUARE TUBE POST	39.000	LF
0580	854(A)6201	(SP) TRAFFIC STRIPE(PAINT)(4" WIDE)	6,373.000	LF
0590	854(B)6311	(SP) TRAFFIC STRIPE(PAINT)(WORDS)	15.000	EA
0600	854(B)6321	(SP) TRAFFIC STRIPE(PAINT)(SYMBOLS)	12.000	EA
0610	856(A)8201	(SP) TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	990.000	LF
0620	856(A)8210	(SP) TRAFFIC STRIPE(MULTI-POLY.)(8" WIDE)	70.000	LF
0630	856(A)8218	(SP) TRAFFIC STRIPE(MULTI-POLY.)(24" WIDE)	163.000	LF
0640	856(B)8306	(SP) TRAFFIC STRIPE(MULTI-POLY.)(ARROWS)	6.000	EA
0650	856(B)8314	(SP) TRAFFIC STRIPE(MULTI-POLY.)(WORDS)	1.000	EA
0660	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	2,940.000	LF
0670	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	200.000	LF
0680	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	200.000	LF
0690	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,100.000	SD
0700	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,200.000	SD
0710	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	500.000	SD
0720	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	4,250.000	SD
0730	880(E)6600	WARNING LIGHTS(TYPE A)	8,500.000	SD
0740	880(F)6700	DRUMS	200.000	SD
0005	STAKING			
0750	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0760	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0770	641 2110	MOBILIZATION	1.000	LSUM

Proposal:250039 **Let Date:**January 16, 2025 **Call Order:**206
J/P Num:36593(04) **Proj. Num:**STP-219N(131)IG
Counties:CREEK
Description:SAFETY IMPROVEMENT (STREETSCAPE)
CITY STREET (DEWEY AVENUE/SH-66): FROM MAIN STREET,
EXTEND EAST IN THE CITY OF SAPULPA.
PROJECT LENGTH = 0.3293 MILES

Line #		Item Description	Quantity	Unit
0007	UTILITIES (NON-PARTICIPATING)			
0780	611(A)7251	(PL) PRECAST CONC RND 4' DIA MANHOLE	10.000	EA
0790	611(B)7241	(PL) ADD'L DEPTH PRECAST RND 4' MANHOLE	3.000	VF
0800	612(A)3201	(PL) MANHOLES ADJUST TO GRADE	2.000	EA
0810	613(S)7700	STANDARD BEDDING MATERIAL, CLASS B	652.000	CY
0820	613(V)8000	TRENCH EXCAVATION	765.000	CY
0830	615(A)1220	8" POLYVINYL CHLORIDE (PVC) PIPE	728.000	LF
0840	615(A)1224	10" POLYVINYL CHLORIDE (PVC) PIPE	63.000	LF
0850	615(D)1500	SEWER LEAKAGE < 24" DIAMETER	791.000	LF
0860	615(E)1600	DEFLECTION TEST (< 24" DIAMETER)	1.000	LSUM
0870	616(B)2336	6" POLYVINYL CHLORIDE (PVC) PIPE	702.000	LF
0880	616(D)2646	6" GATE VALVE	4.000	EA
0890	616(G)3111	FIRE HYDRANT AND ASSEMBLY	2.000	EA
0900	616(O)3905	FITTINGS	1.000	EA
0910	616(O)3985	6" 45 DEGREE FITTING	4.000	EA
0920	616(O)3990	6" 90 DEGREE FITTING	1.000	EA
0930	616(S)4405	6" PLUG	2.000	EA
0940	616(T)4530	6" X 6" CROSS	1.000	EA
0950	616(T)4535	6" X 6" X 6" TEE	2.000	EA
0960	619(B)6372	REMOVAL OF MANHOLES	1.000	EA
0970	619(B)6440	REMOVAL OF EXISTING PIPE	749.000	LF
0980	619(B)6504	REMOVE AND RELOCATE UTILITIES	1.000	LSUM