Proposal: 250041 **Let Date:** June 19, 2025 **Call Order:** 410
J/P Num: 36103(04) **Proj. Num:** STP-215D(058)CI
Counties: COAL
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-1669/OLD SH 3):
OVER CANEY CREEK, 2.3 MILES NORTHWEST
OF THE US-75 / SH-3 INTERSECTION NEAR CENTRAHOMA.
PROJECT LENGTH = 0.208 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	2,003.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	1,925.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	854.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	84.000	LF
0070	230(A)7200	SOLID SLAB SODDING	3,791.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	0.780	AC
0090	303(A)1200	AGGREGATE BASE TYPE A	706.000	CY
0100	325 0100	SEPARATOR FABRIC	3,542.000	SY
0110	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	305.000	TON
0120	407(B)7300	TACK COAT	223.000	GAL
0130	408 8100	PRIME COAT	2,057.000	GAL
0140	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	473.000	TON
0150	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	337.000	TON
0160	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0170	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	2,158.000	SY
0180	619(C)6600	SAWING PAVEMENT	42.000	LF
0190	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	50.000	LF
0200	623(F)1704	GUARDRAIL ANCHOR UNIT (TYPE A)	2.000	EA
0210	623(F)1712	GUARDRAIL ANCHOR UNIT (TYPE B)	2.000	EA
0220	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA

Proposal:250041 **Let Date:**June 19, 2025 **Call Order:**410
J/P Num:36103(04) **Proj. Num:**STP-215D(058)CI
Counties:COAL
Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW-1669/OLD SH 3):
OVER CANEY CREEK, 2.3 MILES NORTHWEST
OF THE US-75 / SH-3 INTERSECTION NEAR CENTRAHOMA.
PROJECT LENGTH = 0.208 MILES

	Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A' - NBI NO. 33425				
	0230	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	100.000	CY
	0240	501(G)1800	CLSM BACKFILL	70.000	CY
	0250	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	299.000	LF
	0260	504(A)5200	APPROACH SLAB	115.000	SY
	0270	504(B)5300	SAW-CUT GROOVING	334.500	SY
	0280	504(D)5410	CONCRETE RAIL (TR3)	264.600	LF
	0290	506(A)7200	STRUCTURAL STEEL	100.000	LB
	0300	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	6.000	EA
	0310	509(A)0210	CLASS AA CONCRETE	101.000	CY
	0320	509(B)0320	CLASS A CONCRETE	41.800	CY
	0330	511(A)2210	REINFORCING STEEL	25,380.000	LB
	0340	514(A)5210	PILES, FURNISHED (HP 10X42)	434.000	LF
	0350	514(B)5310	PILES, DRIVEN (HP 10X42)	434.000	LF
	0360	514(K)6200	(PL)PILOT HOLES	140.000	LF
	0370	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
	0380	523(A)3200	SEALER CRACK PREPARATION	100.000	LF
	0390	523(B)3300	SEALER RESIN	1.000	GAL
	0400	601(B)1230	TYPE I-A PLAIN RIPRAP	1,480.000	TON
	0410	601(C)1310	TYPE I-A FILTER BLANKET	225.000	TON
	0420	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	52.000	LF
	0430	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	36.000	LF
	0440	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	SIGNING, STRIPING, SAFETY				
	0450	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
	0460	850(A)1200	SHEET ALUMINUM SIGNS	16.000	SF
	0470	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	4.000	EA
	0480	855(A)7201	(SP) TRAFFIC STRIPE(PLASTIC)(4" WIDE)	2,475.000	LF
0004	TRAFFIC CONTROL				
	0490	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,800.000	SD
	0500	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	720.000	SD
	0510	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	720.000	SD
	0520	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	720.000	SD
	0530	880(E)6600	WARNING LIGHTS(TYPE A)	3,240.000	SD
	0540	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	388.000	SD
0005	STAKING				
	0550	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION				
	0560	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	0570	641 2100	MOBILIZATION	1.000	LSUM