Proposal: 250042 **Let Date:** February 13, 2025 **Call Order:** 310
J/P Num: 36290(04) **Proj. Num:** SBR-217C(056)SB
Counties: COTTON
Description: BRIDGE REHABILITATION
US-70: OVER CACHE CREEK, 12.5 MILES EAST OF I-44
(H.E. BAILEY TURNPIKE) NEAR RANDLETT.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	50.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	100.000	CY
0030	221(B)2300	TEMPORARY SILT FENCE	1,593.000	LF
0040	230(A)7200	SOLID SLAB SODDING	2,000.000	SY
0050	310(B)5300	SUBGRADE, METHOD B	577.000	SY
0060	407(A)7200	FOG SEAL	323.000	GAL
0070	407(B)7300	TACK COAT	268.000	GAL
0080	408 8100	PRIME COAT	173.000	GAL
0090	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	70.000	TON
0100	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	578.000	TON
0110	412 3100	COLD MILLING PAVEMENT	3,140.000	SY
0120	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	305.000	SY
0130	619(B)6396	REMOVAL OF GUARDRAIL	641.000	LF
0140	619(C)6600	SAWING PAVEMENT	671.000	LF
0150	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	400.000	LF
0160	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0170	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0180	625(B)4300	REMOVE AND RECONSTRUCT FENCE	400.000	LF

Proposal:250042 **Let Date:**February 13, 2025 **Call Order:**310
J/P Num:36290(04) **Proj. Num:**SBR-217C(056)SB
Counties:COTTON
Description:BRIDGE REHABILITATION
US-70: OVER CACHE CREEK, 12.5 MILES EAST OF I-44
(H.E. BAILEY TURNPIKE) NEAR RANDLETT.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A'			
0190	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	45.000	CY
0200	501(G)1800	CLSM BACKFILL	122.000	CY
0210	502(B)3310	FALSEWORK AND JACKING	1.000	LSUM
0220	504(A)5200	APPROACH SLAB	214.800	SY
0230	504(B)5300	SAW-CUT GROOVING	1,580.000	SY
0240	504(D)5420	CONCRETE RAIL (TR4)	946.200	LF
0250	506(A)7200	STRUCTURAL STEEL	25,000.000	LB
0260	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	15.000	EA
0270	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	35.000	EA
0280	509(A)0210	CLASS AA CONCRETE	350.100	CY
0290	509(B)0320	CLASS A CONCRETE	407.100	CY
0300	509(D)0510	CLASS C CONCRETE	12.000	CY
0310	511 2100	MECHANICAL SPLICES	1,450.000	EA
0320	511(A)2210	REINFORCING STEEL	2,340.000	LB
0330	511(B)2310	EPOXY COATED REINFORCING STEEL	133,020.000	LB
0340	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0350	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0360	513(B)4300	CLASS B BRIDGE DECK REPAIR	40.000	SY
0370	513(C)4400	CLASS C BRIDGE DECK REPAIR	40.000	SY
0380	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	1,103.000	SY
0390	516(A)8255	DRILLED SHAFTS 84" DIAMETER	256.000	LF
0400	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
0410	517 9110	ELASTOMERIC COATING	2,195.000	SF
0420	518(B)0300	SEALED EXPANSION JOINTS	66.340	LF
0430	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	40.000	LF
0440	520(C)1400	EPOXY RESIN, ABOVE WATER	4.000	GAL
0450	521(A)2200	PNEUMATICALLY PLACED MORTAR	40.000	SY
0460	523(A)3200	SEALER CRACK PREPARATION	568.000	LF
0470	523(B)3300	SEALER RESIN	5.700	GAL
0480	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	60.000	SY
0490	535 7110	HAUL AND ERECT STEEL BEAMS	1.000	LSUM
0500	601(A)1110	TYPE I PLAIN RIPRAP	500.000	TON
0510	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0003	SIGNING AND STRIPING			
0520	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	1,080.000	LF
0530	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	12.000	EA
0540	856(A)8206	(SP) TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	3,175.000	LF

Proposal:250042 **Let Date:**February 13, 2025 **Call Order:**310
J/P Num:36290(04) **Proj. Num:**SBR-217C(056)SB
Counties:COTTON
Description:BRIDGE REHABILITATION
US-70: OVER CACHE CREEK, 12.5 MILES EAST OF I-44
(H.E. BAILEY TURNPIKE) NEAR RANDLETT.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
0550	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	311.000	SD
0560	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	5,024.000	LF
0570	857(C)9410	REMOVABLE PAVEMENT MARKING TAPE(8" WIDE)	44.000	LF
0580	871(B)2300	CONST.ZONE IMPACT ATTEN.	621.000	SD
0590	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,150.000	LF
0600	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,150.000	LF
0610	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	7,544.000	SD
0620	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,991.000	SD
0630	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	8,188.000	SD
0640	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	679.000	SD
0650	880(E)6600	WARNING LIGHTS(TYPE A)	115.000	SD
0660	880(E)6607	WARNING LIGHTS(TYPE B)	7,452.000	SD
0670	880(F)6700	DRUMS	9,269.000	SD
0680	880(I)7000	FLAGGER	23.000	SD
0690	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	661.000	SD
0005	STAKING			
0700	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0710	641 2100	MOBILIZATION	1.000	LSUM