Proposal: 250050 **Let Date:** February 20, 2025 **Call Order:** 400
J/P Num: 35076(04) **Proj. Num:** SSR-201B(062)SR
Counties: ADAIR
Description: RESURFACE (ASPHALT)
US-62: FROM 5.0 MILES NORTHEAST OF THE SH-51 INTERSECTION,
EXTEND EAST NEAR TAHLEQUAH.
PROJECT LENGTH = 6.13 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	407(B)7300	TACK COAT	8,500.000	GAL
0020	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	10,800.000	TON
0030	412 3100	COLD MILLING PAVEMENT	98,000.000	SY
0002	TRAFFIC			
0040	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	5,010.000	LF
0050	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	10,300.000	LF
0060	856(A)8201	(SP) TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	129,500.000	LF
0070	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	720.000	SD
0080	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,170.000	SD
0090	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,665.000	SD
0100	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	450.000	SD
0110	880(E)6600	WARNING LIGHTS(TYPE A)	2,520.000	SD
0120	880(F)6700	DRUMS	585.000	SD
0130	880(G)6805	CHANNELIZER CONES	16,200.000	SD
0140	880(I)7000	FLAGGER	45.000	SD
0150	880(W)7700	PILOT CAR	1.000	LSUM
0160	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	104.000	SD