**Letting Date:** February 13, 2025, 10:30 A.M.
**Call Order:** 430 **Contract ID:** 250056
**J/P No.:** 35151(04) **Project No.:** SSR-230B(069)SR **Contract Time:**
**County:** HARPER
**Description:** RESURFACE (ASPHALT)
SH-34: 11.2 MILES NORTH OF THE US-412 INTERSECTION,
EXTEND NORTH NEAR WOODWARD.
PROJECT LENGTH = 10.90 MILES

| | VENDORNAME | PROPOSALITEMTO | | |
|---|---|---|---|---|
| 1 | THE CUMMINS CONSTRUCTION CO., INC. | 2,824,760.50 | 83.78 | 100.00 |
| 2 | J&R Constructors Group | 2,855,497.00 | 84.69 | 101.09 |
| 3 | Overland Corporation | 3,353,798.50 | 99.47 | 118.73 |

**Letting Date:** February 13, 2025, 10:30 A.M.
**Call Order:** 430 **Contract ID:** 250056

| Line # | Item Number | Item Description | Quantity/Unit | |
|---|---|---|---|---|
| | Bidder | | Unit Price | Ext Amount |
| **Section: 0001 ROADWAY** | | | | |
| 0010 | 202(D)2500 | UNCLASSIFIED BORROW | 1,200.000 | CY |
| | **Engineer's Estimate** | | **10.00** | **12,000.00** |
| 1 | THE CUMMINS CONSTRUCTION CO., INC. | | 12.55 | 15,060.00 |
| 2 | J&R Constructors Group | | 5.00 | 6,000.00 |
| 3 | Overland Corporation | | 35.00 | 42,000.00 |
| 0020 | 202(H)2900 | EARTHWORK | 1.000 | LSUM |
| | **Engineer's Estimate** | | **65,400.00** | **65,400.00** |
| 1 | THE CUMMINS CONSTRUCTION CO., INC. | | 48,450.00 | 48,450.00 |
| 2 | J&R Constructors Group | | 36,000.00 | 36,000.00 |
| 3 | Overland Corporation | | 158,000.00 | 158,000.00 |
| 0030 | 407(C)7400 | (SP) POLYMER MOD. CATIONIC RAPID SET - 1S | 40,000.000 | GAL |
| | **Engineer's Estimate** | | **4.00** | **160,000.00** |
| 1 | THE CUMMINS CONSTRUCTION CO., INC. | | 3.00 | 120,000.00 |
| 2 | J&R Constructors Group | | 3.00 | 120,000.00 |
| 3 | Overland Corporation | | 2.75 | 110,000.00 |
| 0040 | 411(C)1430 | SUPERPAVE, TYPE S4(PG 64-22 OK) | 17,900.000 | TON |
| | **Engineer's Estimate** | | **150.00** | **2,685,000.00** |
| 1 | THE CUMMINS CONSTRUCTION CO., INC. | | 123.00 | 2,201,700.00 |
| 2 | J&R Constructors Group | | 130.00 | 2,327,000.00 |
| 3 | Overland Corporation | | 142.00 | 2,541,800.00 |
| 0050 | 411(I)2000 | SUPERPAVE, TYPE S4(PATCH)(PG64-22OK) | 400.000 | TON |
| | **Engineer's Estimate** | | **240.00** | **96,000.00** |
| 1 | THE CUMMINS CONSTRUCTION CO., INC. | | 190.75 | 76,300.00 |
| 2 | J&R Constructors Group | | 235.00 | 94,000.00 |
| 3 | Overland Corporation | | 380.00 | 152,000.00 |
| 0060 | 412 3100 | COLD MILLING PAVEMENT | 2,200.000 | SY |
| | **Engineer's Estimate** | | **5.00** | **11,000.00** |
| 1 | THE CUMMINS CONSTRUCTION CO., INC. | | 7.90 | 17,380.00 |
| 2 | J&R Constructors Group | | 5.00 | 11,000.00 |
| 3 | Overland Corporation | | 7.00 | 15,400.00 |

| Line # | Item Number | Item Description | Quantity/Unit | |
|---|---|---|---|---|
| | Bidder | | Unit Price | Ext Amount |
| **Section: 0002 TRAFFIC** | | | | |
| 0070 | 856(A)8207 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE) | 187,050.000 | LF |
| | **Engineer's Estimate** | | **0.80** | **149,640.00** |
| 1 | THE CUMMINS CONSTRUCTION CO., INC. | | 0.80 | 149,640.00 |
| 2 | J&R Constructors Group | | 0.54 | 101,007.00 |
| 3 | Overland Corporation | | 0.77 | 144,028.50 |
| 0080 | 880(J)7100 | (SP) CONSTRUCTION TRAFFIC CONTROL | 45.000 | SD |
| | **Engineer's Estimate** | | **100.00** | **4,500.00** |
| 1 | THE CUMMINS CONSTRUCTION CO., INC. | | 250.00 | 11,250.00 |
| 2 | J&R Constructors Group | | 100.00 | 4,500.00 |
| 3 | Overland Corporation | | 250.00 | 11,250.00 |

**Letting Date:** February 13, 2025, 10:30 A.M.

**Call Order:** 430 **Contract ID:** 250056

| Line # | Item Number | Item Description | Quantity/Unit |
|---|---|---|---|
| | Bidder | Unit Price | Ext Amount |
| **Section: 0002 TRAFFIC** | | | |
| 0090 | 882(A)8210 | PORT.CHANGEABLE MESSAGE SIGN | 90.000 SD |
| | **Engineer's Estimate** | **40.00** | **3,600.00** |
| 1 | THE CUMMINS CONSTRUCTION CO., INC. | 48.75 | 4,387.50 |
| 2 | J&R Constructors Group | 11.00 | 990.00 |
| 3 | Overland Corporation | 48.00 | 4,320.00 |

| Line # | Item Number | Item Description | Quantity/Unit |
|---|---|---|---|
| | Bidder | Unit Price | Ext Amount |
| **Section: 0003 CONSTRUCTION** | | | |
| 0100 | 641 2110 | MOBILIZATION | 1.000 LSUM |
| | **Engineer's Estimate** | **184,500.00** | **184,500.00** |
| 1 | THE CUMMINS CONSTRUCTION CO., INC. | 180,593.00 | 180,593.00 |
| 2 | J&R Constructors Group | 155,000.00 | 155,000.00 |
| 3 | Overland Corporation | 175,000.00 | 175,000.00 |