Proposal: 250056 **Let Date:** February 13, 2025 **Call Order:** 430
J/P Num: 35151(04) **Proj. Num:** SSR-230B(069)SR
Counties: HARPER
Description: RESURFACE (ASPHALT)
SH-34: 11.2 MILES NORTH OF THE US-412 INTERSECTION,
EXTEND NORTH NEAR WOODWARD.
PROJECT LENGTH = 10.90 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(D)2500	UNCLASSIFIED BORROW	1,200.000	CY
0020	202(H)2900	EARTHWORK	1.000	LSUM
0030	407(C)7400	(SP) POLYMER MOD. CATIONIC RAPID SET - 1S	40,000.000	GAL
0040	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	17,900.000	TON
0050	411(I)2000	SUPERPAVE, TYPE S4(PATCH)(PG64-22OK)	400.000	TON
0060	412 3100	COLD MILLING PAVEMENT	2,200.000	SY
0002	TRAFFIC			
0070	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	187,050.000	LF
0080	880(J)7100	(SP) CONSTRUCTION TRAFFIC CONTROL	45.000	SD
0090	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	90.000	SD
0003	CONSTRUCTION			
0100	641 2110	MOBILIZATION	1.000	LSUM