Proposal: 250063 **Let Date:** May 15, 2025 **Call Order:** 205
J/P Num: 35662(04) **Proj. Num:** STP-207C(130)AD
Counties: BRYAN
Description: PEDESTRIAN IMPROVEMENTS (SIDEWALK)
SH-22: FROM 0.1 MI EAST OF THE US-69 INTERSECTION,
EXTEND EAST IN CADDO.
PROJECT LENGTH = 1.048 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	201(B)1300	SELECTIVE CLEARING	1.000	LSUM
0030	202(A)2200	UNCLASSIFIED EXCAVATION	71.250	CY
0040	202(D)2500	UNCLASSIFIED BORROW	97.500	CY
0050	221(B)2300	TEMPORARY SILT FENCE	4,182.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	7.000	LF
0070	230(A)7200	SOLID SLAB SODDING	2,938.000	SY
0080	232(B)9300	SEEDING METHOD B	0.580	AC
0090	233(A)0200	VEGETATIVE MULCHING	0.580	AC
0100	303(A)1200	AGGREGATE BASE TYPE A	109.250	CY
0110	609(B)4330	1'-8" COMB.CRB.& GUT.(6" BARRIER)	230.000	LF
0120	609(C)4400	CONCRETE HEADER CURB (6"X 16")	365.000	LF
0130	610(A)5200	4" CONCRETE SIDEWALK	2,719.750	SY
0140	610(A)5220	6" CONCRETE SIDEWALK	426.010	SY
0150	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	570.000	SY
0160	610(I)6000	TACTILE WARNING DEVICE-NEW	417.000	SF
0170	611(G)7700	SPECIAL INLET DRAIN	6.000	EA
0180	613(E)5900	18" CORRUGATED POLYETHYLENE PIPE	16.000	LF
0190	613(EE)5965	15" CORRUGATED POLYPROPYLENE PIPE	5.000	LF
0200	613(L)6704	15" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0210	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0220	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0230	619(B)6356	REMOVAL OF CURB AND GUTTER	12.000	LF
0240	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	130.000	SY
0250	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	242.000	SY
0260	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	335.000	SY
0270	619(B)6404	REMOVAL OF SIDEWALK	1,154.000	SY
0280	619(B)6440	REMOVAL OF EXISTING PIPE	30.000	LF
0290	619(C)6600	SAWING PAVEMENT	725.000	LF
0300	622(A)0210	1 1/2" PIPE RAILING	417.000	LF
0310	629(D)7500	REMOVE AND RESET MAILBOX	2.000	EA
0002	TRAFFIC			
0320	805(D)3504	(PL)REMOVE & RESET LIGHT POLE	5.000	EA
0330	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	4.000	EA
0340	836 7100	REGULATORY OR WARNING SIGN ASSEMBLY	4.000	EA
0350	850(A)1200	SHEET ALUMINUM SIGNS	95.000	SF
0360	851(C)2415	2" SQUARE TUBE POST	22.000	LF
0370	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	685.000	LF

Proposal: 250063 **Let Date:** May 15, 2025 **Call Order:** 205
J/P Num: 35662(04) **Proj. Num:** STP-207C(130)AD
Counties: BRYAN
Description: PEDESTRIAN IMPROVEMENTS (SIDEWALK)
SH-22: FROM 0.1 MI EAST OF THE US-69 INTERSECTION,
EXTEND EAST IN CADDO.
PROJECT LENGTH = 1.048 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0380	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,760.000	SD
0390	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,415.000	SD
0400	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	4,485.000	SD
0410	880(E)6607	WARNING LIGHTS(TYPE B)	43,125.000	SD
0420	880(G)6805	CHANNELIZER CONES	39,392.450	SD
0430	880(I)7000	FLAGGER	50.000	SD
0004	STAKING			
0440	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0450	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0460	641 2110	MOBILIZATION	1.000	LSUM