Proposal: 250066 **Let Date:** April 17, 2025 **Call Order:** 820
J/P Num: 34545(04) **Proj. Num:** STP-211D(101)CI
Counties: CHEROKEE
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-68/SH-82B): OVER FOURTEEN MILE CREEK, 1.98 MILES WEST OF SH-10 IN MOODYS.
PROJECT LENGTH = 0.234 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	2,114.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	5,288.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	1,754.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	77.000	LF
0070	230(A)7200	SOLID SLAB SODDING	3,845.000	SY
0080	233(A)0200	VEGETATIVE MULCHING	0.800	AC
0090	307(K)4200	STABILIZED SUBGRADE	3,331.000	SY
0100	326(B)1300	GEOGRID REINFORCEMENT	2,130.000	SY
0110	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	90.000	TON
0120	407(B)7300	TACK COAT	281.000	GAL
0130	408 8100	PRIME COAT	1,177.000	GAL
0140	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	790.000	TON
0150	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	458.000	TON
0160	509(D)0500	CLASS C CONCRETE	36.000	CY
0170	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	256.000	LF
0180	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	46.000	LF
0190	613(M)6960	TYPE A4 CULVERT END TREATMENT	2.000	EA
0200	613(M)6984	TYPE BB4 CULVERT END TREATMENT	4.000	EA
0210	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0220	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	3,153.000	SY
0230	619(B)6440	REMOVAL OF EXISTING PIPE	329.000	LF
0240	619(B)6472	REMOVAL OF EXISTING SLAB	332.000	SY
0250	619(C)6600	SAWING PAVEMENT	208.000	LF
0260	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	65.000	LF
0270	623(F)1704	GUARDRAIL ANCHOR UNIT (TYPE A)	3.000	EA
0280	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0290	624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	834.000	LF
0300	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	420.000	LF
0310	629(A)7200	MAILBOX INSTALLATION-SINGLE	1.000	EA
0320	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	1.000	EA
0330	629(E)7600	MAILBOX	1.000	EA

Proposal:250066 **Let Date:**April 17, 2025 **Call Order:**820
J/P Num:34545(04) **Proj. Num:**STP-211D(101)CI
Counties:CHEROKEE
Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW-68/SH-82B): OVER FOURTEEN MILE CREEK, 1.98 MILES WEST OF SH-10 IN MOODYS.
PROJECT LENGTH = 0.234 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE 'A' - NBI NO.33204			
0340	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	200.000	CY
0350	501(G)1800	CLSM BACKFILL	88.000	CY
0360	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	239.000	LF
0370	504(A)5200	APPROACH SLAB	156.600	SY
0380	504(B)5300	SAW-CUT GROOVING	327.900	SY
0390	504(D)5410	CONCRETE RAIL (TR3)	233.300	LF
0400	506(A)7200	STRUCTURAL STEEL	320.000	LB
0410	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	3.000	EA
0420	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	3.000	EA
0430	509(A)0210	CLASS AA CONCRETE	65.900	CY
0440	509(B)0320	CLASS A CONCRETE	74.200	CY
0450	511(A)2210	REINFORCING STEEL	28,100.000	LB
0460	514(A)5210	PILES, FURNISHED (HP 10X42)	96.000	LF
0470	514(A)5220	PILES, FURNISHED (HP 12X53)	198.000	LF
0480	514(B)5310	PILES, DRIVEN (HP 10X42)	96.000	LF
0490	514(B)5320	PILES, DRIVEN (HP 12X53)	198.000	LF
0500	514(K)6200	(PL)PILOT HOLES	75.000	LF
0510	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0520	601(B)1230	TYPE I-A PLAIN RIPRAP	420.000	TON
0530	601(C)1310	TYPE I-A FILTER BLANKET	110.000	TON
0540	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	60.000	LF
0550	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	61.000	LF
0003	TRAFFIC			
0560	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	3.000	EA
0570	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
0580	850(A)1200	SHEET ALUMINUM SIGNS	10.000	SF
0590	851(C)2415	2" SQUARE TUBE POST	28.000	LF
0600	856(A)8201	(SP) TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE)	2,476.000	LF
0610	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,040.000	SD
0620	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	480.000	SD
0630	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	380.000	SD
0640	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	510.000	SD
0650	880(E)6600	WARNING LIGHTS(TYPE A)	340.000	SD
0660	880(F)6700	DRUMS	130.000	SD
0670	880(I)7000	FLAGGER	10.000	SD
0004	STAKING			
0680	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0690	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0700	641 2100	MOBILIZATION	1.000	LSUM