Proposal: 250070 **Let Date:** June 12, 2025 **Call Order:** 330
J/P Num: 35684(04) **Proj. Num:** NHPP-236N(132)3P
Counties: KAY
Description: RESURFACE (ASPHALT)
US-77: FROM 0.03 MILES SOUTH OF HARTFORD AVENUE,
EXTEND NORTH IN PONCA CITY.
PROJECT LENGTH = 1.690 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	303(A)1200	AGGREGATE BASE TYPE A	100.000	CY
0020	407(C)7500	NT TACK MATERIAL	6,600.000	GAL
0030	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	7,300.000	TON
0040	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	300.000	TON
0050	412 3100	COLD MILLING PAVEMENT	63,500.000	SY
0060	609(B)4360	2'-8" COMB.CRB.& GUT.(6" BARRIER)	100.000	LF
0070	619(B)6356	REMOVAL OF CURB AND GUTTER	100.000	LF
0080	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	300.000	SY
0090	619(B)6376	REMOVAL OF CONC.PAV.W/ASPH.OVERLAY	300.000	SY
0100	619(C)6600	SAWING PAVEMENT	1,500.000	LF
0002	TRAFFIC			
0120	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	30,200.000	LF
0130	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	4,000.000	LF
0140	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	1,300.000	LF
0150	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	620.000	LF
0160	856(B)8303	(SP) TRAF.STR.(PLURAL-COMPONENT)(SYM,WRD,ETC)	80.000	EA
0170	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	3,000.000	LF
0180	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	5,000.000	EA
0190	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	6,000.000	LF
0200	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	20.000	EA
0210	876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	120.000	SD
0220	880(A)6220	ARROW DISPLAY(TYPE C)	120.000	SD
0230	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	6,000.000	SD
0240	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,000.000	SD
0250	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	5,000.000	SD
0260	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,000.000	SD
0270	880(C)6420	WING BARRICADES	720.000	SD
0280	880(E)6607	WARNING LIGHTS(TYPE B)	14,000.000	SD
0290	880(F)6700	DRUMS	6,000.000	SD
0300	880(G)6805	CHANNELIZER CONES	6,000.000	SD
0310	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	700.000	HOUR
0320	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	240.000	SD
0003	CONSTRUCTION			
0330	641 2110	MOBILIZATION	1.000	LSUM