**Proposal:** 250072 **Let Date:** March 13, 2025 **Call Order:** 550
**J/P Num:** 33546(04) **Proj. Num:** STP-243D(052)CI
**Counties:** LOVE
**Description:** GRADE, DRAIN AND SURFACE
COUNTY ROAD (TURKEY HATCHERY RD/EW-2125):
FROM 1.22 MILES EAST OF US-77,
EXTEND EAST IN MARIETTA.
PROJECT LENGTH = 1.292 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0001** | ROADWAY | | | |
| 0010 | 201(A)1200 | CLEARING AND GRUBBING | 1.000 | LSUM |
| 0020 | 202(A)2200 | UNCLASSIFIED EXCAVATION | 11,266.000 | CY |
| 0030 | 205(A)6200 | TYPE A-SALVAGED TOPSOIL | 1.000 | LSUM |
| 0040 | 221(B)2300 | TEMPORARY SILT FENCE | 81.000 | LF |
| 0050 | 221(E)2600 | TEMPORARY SILT DIKE | 931.000 | LF |
| 0060 | 221(F)2710 | TEMPORARY ROCK FILTER DAM TYPE 2 | 80.000 | CY |
| 0070 | 230(A)7200 | SOLID SLAB SODDING | 53,325.000 | SY |
| 0080 | 233(A)0200 | VEGETATIVE MULCHING | 18.460 | AC |
| 0090 | 233(F)0700 | (SP) HYDROSEED | 5,333.000 | SY |
| 0100 | 303(A)1210 | AGGREGATE BASE TYPE A, PLANT MIXED | 3,271.000 | CY |
| 0110 | 307(K)4200 | STABILIZED SUBGRADE | 18,483.000 | SY |
| 0120 | 402(E)2600 | TRAFFIC BOUND SURFACE COURSE TYPE E | 846.000 | TON |
| 0130 | 408 8100 | PRIME COAT | 6,786.000 | GAL |
| 0140 | 501(A)1200 | STRUCTURAL EXCAVATION UNCLASSIFIED | 34.000 | CY |
| 0150 | 509(A)0200 | CLASS AA CONCRETE | 106.000 | CY |
| 0160 | 509(D)0500 | CLASS C CONCRETE | 50.000 | CY |
| 0170 | 511(A)2200 | REINFORCING STEEL | 15,614.000 | LB |
| 0180 | 601(B)1200 | TYPE I PLAIN RIPRAP WITH FILTER BLANKET | 44.000 | TON |
| 0190 | 602(B)2310 | REVETMENT MATTRESSES | 2,196.000 | SY |
| 0200 | 613(A)5220 | 30" R.C.PIPE CLASS III | 32.000 | LF |
| 0210 | 613(A)5232 | 48" R.C.PIPE CLASS III | 38.000 | LF |
| 0220 | 613(A)5240 | 60" R.C.PIPE CLASS III | 77.000 | LF |
| 0230 | 613(EE)5969 | 18" CORRUGATED POLYPROPYLENE PIPE | 410.000 | LF |
| 0240 | 613(L)6708 | 18" PREFAB. CULVERT END SEC., ROUND | 18.000 | EA |
| 0250 | 613(L)6724 | 30" PREFAB. CULVERT END SEC., ROUND | 2.000 | EA |
| 0260 | 613(L)6736 | 48" PREFAB. CULVERT END SEC., ROUND | 2.000 | EA |
| 0270 | 613(L)6744 | 60" PREFAB. CULVERT END SEC., ROUND | 4.000 | EA |
| 0280 | 619(A)6200 | REMOVAL OF STRUCTURES & OBSTRUCTIONS | 1.000 | LSUM |
| 0290 | 624(C)3400 | FENCE-STYLE SWF (4 BARBED WIRE) | 2,153.000 | LF |
| 0300 | 624(C)3405 | FENCE-STYLE SWF (5 BARBED WIRE) | 218.000 | LF |
| 0310 | 624(C)3410 | FENCE-STYLE SWF (6 BARBED WIRE) | 1,127.000 | LF |
| 0320 | 629(D)7500 | REMOVE AND RESET MAILBOX | 3.000 | EA |
| **0002** | TRAFFIC | | | |
| 0330 | 805(D)3528 | (PL)REMOVE & RESET EXISTING SIGNS | 5.000 | EA |
| 0340 | 850(A)1200 | SHEET ALUMINUM SIGNS | 10.000 | SF |
| 0350 | 851(C)2415 | 2" SQUARE TUBE POST | 20.000 | LF |
| 0360 | 880(B)6300 | CONSTRUCTION SIGNS 0 TO 6.25 SF | 1,242.000 | SD |
| 0370 | 880(B)6310 | CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF | 1,104.000 | SD |
| 0380 | 880(B)6320 | CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF | 276.000 | SD |
| 0390 | 880(C)6410 | CONSTRUCTION BARRICADES(TYPE III) | 552.000 | SD |
| 0400 | 880(E)6600 | WARNING LIGHTS(TYPE A) | 1,380.000 | SD |
| **0003** | STAKING | | | |
| 0410 | 642(B)3300 | CONSTRUCTION STAKING LEVEL II | 1.000 | LSUM |

**Proposal:** 250072 **Let Date:** March 13, 2025 **Call Order:** 550
**J/P Num:** 33546(04) **Proj. Num:** STP-243D(052)CI
**Counties:** LOVE
**Description:** GRADE, DRAIN AND SURFACE
COUNTY ROAD (TURKEY HATCHERY RD/EW-2125):
FROM 1.22 MILES EAST OF US-77,
EXTEND EAST IN MARIETTA.
PROJECT LENGTH = 1.292 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0004** | CONSTRUCTION | | | |
| 0420 | 220 1100 | SWPPP DOCUMENTATION AND MANAGEMENT | 1.000 | LSUM |
| 0430 | 641 2110 | MOBILIZATION | 1.000 | LSUM |