**Proposal:** 250073 **Let Date:** March 13, 2025 **Call Order:** 555
**J/P Num:** 31158(04) **Proj. Num:** CIRB-247C(054)RB
**Counties:** MAJOR
**Description:** PAVEMENT REHABILITATION (ASPHALT)
COUNTY ROAD (EW-58): FROM 7.96 MILES EAST OF US-281, EXTEND EAST NEAR SEILING.
PROJECT LENGTH = 2.534 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0001** | ROADWAY | | | |
| 0010 | 202(D)2500 | UNCLASSIFIED BORROW | 7,000.000 | CY |
| 0020 | 221(B)2300 | TEMPORARY SILT FENCE | 130.000 | LF |
| 0030 | 221(E)2600 | TEMPORARY SILT DIKE | 56.000 | LF |
| 0040 | 230(A)7200 | SOLID SLAB SODDING | 25,273.330 | SY |
| 0050 | 233(A)0200 | VEGETATIVE MULCHING | 5.220 | AC |
| 0060 | 303(A)1200 | AGGREGATE BASE TYPE A | 328.950 | CY |
| 0070 | 303(E)1600 | COLD IN-PLACE RECYCLING | 32,706.670 | SY |
| 0080 | 325 0100 | SEPARATOR FABRIC | 1,271.890 | SY |
| 0090 | 402(E)2600 | TRAFFIC BOUND SURFACE COURSE TYPE E | 1,076.280 | TON |
| 0100 | 407(B)7300 | TACK COAT | 4,196.660 | GAL |
| 0110 | 408 8100 | PRIME COAT | 522.140 | GAL |
| 0120 | 410(A)0260 | CSS-SPECIAL LIQUIFIED EMULSION | 333.800 | TON |
| 0130 | 411(C)1430 | SUPERPAVE, TYPE S4(PG 64-22 OK) | 10,585.300 | TON |
| 0140 | 411(I)2000 | SUPERPAVE, TYPE S4(PATCH)(PG64-22OK) | 100.000 | TON |
| 0150 | 501(G)1810 | CLSM BACKFILL | 20.000 | CY |
| 0160 | 509(D)0500 | CLASS C CONCRETE | 20.000 | CY |
| 0170 | 613(A)5358 | 28" X 18" R.C.PIPE ARCH CLASS A-III | 208.000 | LF |
| 0180 | 613(M)6924 | TYPE BB3 CULVERT END TREATMENT | 4.000 | EA |
| 0190 | 619(A)6200 | REMOVAL OF STRUCTURES & OBSTRUCTIONS | 1.000 | LSUM |
| 0200 | 619(C)6600 | SAWING PAVEMENT | 44.000 | LF |
| **0002** | TRAFFIC | | | |
| 0210 | 850(A)1200 | SHEET ALUMINUM SIGNS | 15.540 | SF |
| 0220 | 856(A)8201 | (SP) TRAFFIC STRIPE(MULTI-POLY.)(4" WIDE) | 21,947.500 | LF |
| 0230 | 880(B)6300 | CONSTRUCTION SIGNS 0 TO 6.25 SF | 2,700.000 | SD |
| 0240 | 880(B)6310 | CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF | 900.000 | SD |
| 0250 | 880(B)6320 | CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF | 3,240.000 | SD |
| 0260 | 880(C)6410 | CONSTRUCTION BARRICADES(TYPE III) | 1,170.000 | SD |
| 0270 | 880(E)6600 | WARNING LIGHTS(TYPE A) | 1,170.000 | SD |
| 0280 | 880(I)7000 | FLAGGER | 90.000 | SD |
| **0003** | CONSTRUCTION | | | |
| 0290 | 220 1100 | SWPPP DOCUMENTATION AND MANAGEMENT | 1.000 | LSUM |
| 0300 | 641 2110 | MOBILIZATION | 1.000 | LSUM |