Proposal:250077 **Let Date:**August 07, 2025 **Call Order:**785
J/P Num:28846(04) **Proj. Num:**STP-172E(540)EH
Counties:TULSA
Description:SIDEWALK IMPROVEMENTS
CITY STREETS: AT MULTIPLE LOCATIONS
IN THE CITY OF TULSA.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	377.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	130.000	CY
0040	221(B)2300	TEMPORARY SILT FENCE	735.000	LF
0050	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	18.000	EA
0060	230(A)7200	SOLID SLAB SODDING	1,124.000	SY
0070	303(A)1200	AGGREGATE BASE TYPE A	183.000	CY
0080	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	15.000	TON
0090	412 3100	COLD MILLING PAVEMENT	142.000	SY
0100	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	60.000	SY
0110	414(G)5800	P.C. CONCRETE FOR PAVEMENT	14.000	CY
0120	509(A)0200	CLASS AA CONCRETE	3.000	CY
0130	509(D)0500	CLASS C CONCRETE	5.000	CY
0140	511(A)2200	REINFORCING STEEL	436.000	LB
0150	601(A)1100	TYPE I PLAIN RIPRAP	8.000	TON
0160	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	188.000	LF
0170	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	1,987.000	LF
0180	610(A)5200	4" CONCRETE SIDEWALK	2,171.000	SY
0190	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	519.000	SY
0200	610(I)6000	TACTILE WARNING DEVICE-NEW	560.000	SF
0210	611(A)7210	MANHOLE (4' DIA.)	1.000	EA
0220	612(E)3600	VALVE BOXES ADJUST TO GRADE	5.000	EA
0230	613(EE)5961	12" CORRUGATED POLYPROPYLENE PIPE	110.000	LF
0240	613(EE)5965	15" CORRUGATED POLYPROPYLENE PIPE	87.000	LF
0250	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	20.000	LF
0260	613(L)6700	12" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0270	613(L)6704	15" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0280	613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0290	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0300	619(B)6356	REMOVAL OF CURB AND GUTTER	430.000	LF
0310	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	179.000	SY
0320	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	313.000	SY
0330	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	62.000	SY
0340	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	380.000	SY
0350	619(B)6400	REMOVAL OF CURB	1,493.000	LF
0360	619(B)6404	REMOVAL OF SIDEWALK	975.000	SY
0370	619(B)6420	REMOVAL OF RIPRAP	8.000	SY
0380	619(B)6440	REMOVAL OF EXISTING PIPE	129.000	LF
0390	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	13.000	LF
0400	623(G)1800	GUARDRAIL END TREATMENT (GET)	2.000	EA
0410	624 3100	(PL) ORNAMENTAL FENCE	246.000	LF
0420	624(E)3600	FENCE-STYLE CLF (4'HIGH, CLASS A)	15.000	LF
0430	629(D)7500	REMOVE AND RESET MAILBOX	4.000	EA

Proposal:250077 **Let Date:**August 07, 2025 **Call Order:**785
J/P Num:28846(04) **Proj. Num:**STP-172E(540)EH
Counties:TULSA
Description:SIDEWALK IMPROVEMENTS
CITY STREETS: AT MULTIPLE LOCATIONS
IN THE CITY OF TULSA.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC SIGNAL			
0440	104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	7.000	DAY
0450	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	128.000	LF
0460	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	160.000	LF
0470	803(A)1220	PULL BOX(SIZE II)	1.000	EA
0480	804(A)2200	STRUCTURAL CONCRETE	5.000	CY
0490	804(B)2300	REINFORCING STEEL	434.000	LB
0491	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0492	805(B)3300	(PL)RESET OF PULL BOX	6.000	EA
0500	806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	10.000	EA
0510	830 2100	PEDESTRIAN PUSH BUTTON	2.000	EA
0520	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	10.000	EA
0530	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,025.000	LF
0540	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	195.000	LF
0003	TRAFFIC SIGNING AND STRIPING			
0550	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
0560	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	6.000	EA
0570	850(A)1200	SHEET ALUMINUM SIGNS	37.000	SF
0580	851(C)2415	2" SQUARE TUBE POST	370.000	LF
0590	855(A)7213	(SP) TRAFFIC STRIPE(PLASTIC)(12" WIDE)	1,110.000	LF
0600	855(A)7217	(SP) TRAFFIC STRIPE(PLASTIC)(24" WIDE)	1,177.000	LF
0610	855(B)7313	(SP) TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	10.000	EA
0004	TRAFFIC CONTROL			
0620	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	7,200.000	SD
0630	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,320.000	SD
0640	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,880.000	SD
0650	880(C)6405	CONSTRUCTION BARRICADES(TYPE II)	1,920.000	SD
0660	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,920.000	SD
0670	880(E)6600	WARNING LIGHTS(TYPE A)	32,640.000	SD
0680	880(F)6700	DRUMS	7,200.000	SD
0690	880(G)6805	CHANNELIZER CONES	14,400.000	SD
0005	STAKING			
0700	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0710	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0720	641 2110	MOBILIZATION	1.000	LSUM