Proposal: 250078 **Let Date:** May 15, 2025 **Call Order:** 242
J/P Num: 34436(04) **Proj. Num:** NHPP-030N(085)FP
Counties: TULSA
Description: GRADE, DRAIN, AND SURFACE
US-169: FROM 2.0 MILES NORTH OF THE INTERSECTION OF SH-266, EXTEND NORTH IN OWASSO.
PROJECT LENGTH = 1.282 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	1,158.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	13,160.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	11,764.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	9.000	EA
0070	221(E)2600	TEMPORARY SILT DIKE	1,155.000	LF
0080	230(A)7200	SOLID SLAB SODDING	16,979.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	3.510	AC
0100	241 3100	MOWING	3.510	AC
0110	303(A)1200	AGGREGATE BASE TYPE A	7,551.000	CY
0120	307(K)4200	STABILIZED SUBGRADE	35,973.000	SY
0130	325 0100	SEPARATOR FABRIC	28,313.000	SY
0140	407(B)7300	TACK COAT	19,650.000	GAL
0150	409(A)9200	FABRIC REINFORCEMENT	4,774.000	SY
0160	409(B)9300	BITUMINOUS BINDER	1,973.000	GAL
0170	411(B)1300	SUPERPAVE, TYPE S3(PG 76-28 OK)	9,231.000	TON
0180	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	24,754.000	TON
0190	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	6,154.000	TON
0200	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	4,067.000	TON
0210	412 3100	COLD MILLING PAVEMENT	53,489.000	SY
0220	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	3,281.000	SY
0230	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	8,312.000	SY
0240	414(G)5800	P.C. CONCRETE FOR PAVEMENT	2,899.000	CY
0250	509(B)0310	CLASS A CONCRETE(LONG. BAR. DES. 1-A)	548.000	CY
0260	511(A)2200	REINFORCING STEEL	13,011.000	LB
0270	610(C)5410	6" CONCRETE DIVIDING STRIP	885.000	SY
0280	611(G)0350	INLET (SMD-TYPE 1)	1.000	EA
0290	611(G)8170	INLET - LONG. BARRIER - TYPE II, DES. 1	29.000	EA
0300	611(H)0400	ADDITIONAL DEPTH IN INLET	3.000	VF
0310	611(H)0660	ADD'L DEPTH IN INLET MED. BAR. TYPE II, DES. 1	96.000	VF
0320	612(C)3400	INLET ADJUST TO GRADE	1.000	EA
0330	613(A)5208	18" R.C.PIPE CLASS III	2,818.000	LF
0340	613(A)5216	24" R.C.PIPE CLASS III	1,718.000	LF
0350	613(A)5220	30" R.C.PIPE CLASS III	873.000	LF
0360	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	8,324.000	LF
0370	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	162.000	LF
0380	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0390	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	8,492.000	SY
0400	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	62,153.000	SY
0410	619(C)6600	SAWING PAVEMENT	10,742.000	LF
0420	627(A)6200	CONCRETE LONGITUDINAL BARRIER, DESIGN 1	3,220.000	LF
0430	627(B)6300	CONCRETE LONGITUDINAL BARRIER END SEC.	1.000	EA
0440	871(A)2200	IMPACT ATTENUATOR	3.000	EA

Proposal:250078 **Let Date:**May 15, 2025 **Call Order:**242
J/P Num:34436(04) **Proj. Num:**NHPP-030N(085)FP
Counties:TULSA
Description:GRADE, DRAIN, AND SURFACE
US-169: FROM 2.0 MILES NORTH OF THE INTERSECTION OF SH-266, EXTEND NORTH IN OWASSO.
PROJECT LENGTH = 1.282 MILES

Line #		Item Description	Quantity	Unit
0002	SIGNING AND STRIPING			
0450	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	13,539.000	LF
0460	413(C)4400	RUMBLE STRIP-METHOD PCC-CON	3,940.000	LF
0470	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	10.000	EA
0480	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	46,314.000	LF
0490	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	942.000	LF
0003	TRAFFIC CONTROL			
0500	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	3,733.000	LF
0510	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	198,927.000	LF
0520	857(E)9600	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS	97,924.000	EA
0530	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	3,733.000	LF
0540	871(B)2300	CONST.ZONE IMPACT ATTEN.	90.000	SD
0550	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	15,462.930	LF
0560	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	60,624.260	LF
0570	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	19,080.000	SD
0580	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	7,560.000	SD
0590	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,240.000	SD
0600	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	6,480.000	SD
0610	880(E)6600	WARNING LIGHTS(TYPE A)	9,000.000	SD
0620	880(F)6700	DRUMS	3,024.000	SD
0630	880(G)6805	CHANNELIZER CONES	25,488.000	SD
0004	TRAFFIC LIGHTING			
0640	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	610.000	LF
0650	802(C)0430	2" HIGH DENSITY PE PIPE - TRENCHED	6,400.000	LF
0660	803(A)1200	PULL BOX	29.000	EA
0670	803(A)1210	PULL BOX(SIZE I)	2.000	EA
0680	804(A)2200	STRUCTURAL CONCRETE	141.810	CY
0690	804(B)2300	REINFORCING STEEL	18,241.000	LB
0700	806(C)4524	40' MHP & TWIN H.L.MST.ARM(G.STL.)	29.000	EA
0710	809(A)7200	ROADWAY LUMINAIRE	58.000	EA
0720	810(A)8200	SERVICE POLE	2.000	EA
0730	811 9115	1/C NO.4 ELECT.COND.	21,500.000	LF
0740	811 9135	1/C NO.12 ELECT.COND.	7,250.000	LF
0005	STAKING			
0750	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0760	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0770	640(A)1210	FIELD OFFICE	1.000	EA
0780	641 2110	MOBILIZATION	1.000	LSUM
0007	LIGHTING (NON-PARTICIPATING)			
0790	806(C)4536	POWDER COAT LIGHTING POLE	29.000	EA