Proposal: 250079 **Let Date:** August 14, 2025 **Call Order:** 780
J/P Num: 35484(04) **Proj. Num:** TAP-272B(364)IG
Counties: TULSA
Description: BICYCLE AND PEDESTRIAN IMPROVEMENTS
CITY STREET (N LEWIS AVE):
FROM E 56TH ST N, EXTEND NORTH IN THE CITY OF TULSA.
PROJECT LENGTH = 0.990 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	100.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	100.000	CY
0030	221(B)2300	TEMPORARY SILT FENCE	2,800.000	LF
0040	230(A)7200	SOLID SLAB SODDING	1,644.000	SY
0050	303(A)1200	AGGREGATE BASE TYPE A	73.000	CY
0060	325 0100	SEPARATOR FABRIC	500.000	SY
0070	326(B)1300	GEOGRID REINFORCEMENT	500.000	SY
0080	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	49.000	TON
0090	414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	71.600	SY
0100	414(G)5800	P.C. CONCRETE FOR PAVEMENT	17.000	CY
0110	610(A)5210	5" CONCRETE SIDEWALK	1,219.000	SY
0120	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	349.000	SY
0130	610(I)6000	TACTILE WARNING DEVICE-NEW	140.000	SF
0140	612(I)4000	WATER METER RESET	3.000	EA
0150	616(M)3705	WATER VALVE RISER ADJUST TO GRADE	1.000	EA
0160	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	71.000	SY
0170	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	160.000	SY
0180	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	24.000	SY
0190	619(B)6400	REMOVAL OF CURB	166.000	LF
0200	619(B)6404	REMOVAL OF SIDEWALK	16.000	SY
0002	TRAFFIC			
0210	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	3.000	EA
0220	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	3.000	EA
0230	836 7110	RECTANGULAR RAPID FLASHING BEACON	1.000	EA
0240	850(A)1200	SHEET ALUMINUM SIGNS	82.000	SF
0250	851(C)2415	2" SQUARE TUBE POST	250.000	LF
0260	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	30,963.000	LF
0270	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	2,411.000	LF
0280	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	480.000	LF
0285	856(B)8303	(SP) TRAF.STR.(PLURAL-COMPONENT)(SYM,WRD,ETC)	9.000	EA
0290	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	37.000	EA
0300	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	71.000	EA
0310	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	12,532.000	LF
0320	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	2.000	EA
0330	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	300.000	SD
0340	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,200.000	SD
0350	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	150.000	SD
0360	880(E)6600	WARNING LIGHTS(TYPE A)	26,000.000	SD
0370	880(F)6700	DRUMS	26,000.000	SD
0003	STAKING			
0380	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION			
0390	641 2110	MOBILIZATION	1.000	LSUM