Proposal:250081 **Let Date:**June 12, 2025 **Call Order:**315
J/P Num:32697(04) **Proj. Num:**STP-219C(130)PM
Counties:CREEK
Description:PAVEMENT REHABILITATION (ASPHALT)
SH-66: FROM 3.0 MILES EAST OF US-377, EXTEND EAST NEAR DEPEW.
PROJECT LENGTH = 7.917 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	14,767.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	2,141.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	76,560.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	3,308.000	LF
0070	230(A)7200	SOLID SLAB SODDING	58,016.000	SY
0080	232(B)9300	SEEDING METHOD B	0.420	AC
0090	233(A)0200	VEGETATIVE MULCHING	0.420	AC
0100	241 3100	MOWING	2.660	AC
0110	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	227.000	TON
0120	407(B)7300	TACK COAT	43,478.000	GAL
0130	408 8100	PRIME COAT	4,467.000	GAL
0140	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	33,829.000	TON
0150	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	22,503.000	TON
0160	411(J)2100	(SP) RICH INTERMEDIATE LAYER	21,125.000	TON
0170	412 3100	COLD MILLING PAVEMENT	192,000.000	SY
0180	601(A)1100	TYPE I PLAIN RIPRAP	521.000	TON
0190	601(C)1300	TYPE I-A FILTER BLANKET	131.000	TON
0200	601(F)1610	TYPE IV GROUTED RIPRAP	684.000	SY
0210	613(A)5208	18" R.C.PIPE CLASS III	174.000	LF
0220	613(A)5216	24" R.C.PIPE CLASS III	402.000	LF
0230	613(A)5224	36" R.C.PIPE CLASS III	28.000	LF
0240	613(M)6960	TYPE A4 CULVERT END TREATMENT	4.000	EA
0250	613(M)6964	TYPE B4 CULVERT END TREATMENT	8.000	EA
0260	613(M)6972	TYPE D4 CULVERT END TREATMENT	1.000	EA
0270	613(M)6984	TYPE BB4 CULVERT END TREATMENT	1.000	EA
0280	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0290	619(B)6300	REMOVAL OF HEADWALL	10.000	EA
0300	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	153.000	SY
0310	619(B)6396	REMOVAL OF GUARDRAIL	592.000	LF
0320	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	613.000	LF
0330	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0340	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0350	853 5115	DELINEATORS(TYPE 2, CODE 1)	14.000	EA
0002	TRAFFIC SIGNING AND STRIPING			
0360	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	41,176.000	LF
0370	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	82,351.000	LF
0380	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0390	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	111,489.000	LF

Proposal:250081 **Let Date:**June 12, 2025 **Call Order:**315
J/P Num:32697(04) **Proj. Num:**STP-219C(130)PM
Counties:CREEK
Description:PAVEMENT REHABILITATION (ASPHALT)
SH-66: FROM 3.0 MILES EAST OF US-377, EXTEND EAST NEAR DEPEW.
PROJECT LENGTH = 7.917 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0400	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	253.000	SD
0410	854(A)6201	(SP) TRAFFIC STRIPE(PAINT)(4" WIDE)	5,904.000	LF
0420	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	16,793.000	EA
0450	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	6,324.000	SD
0460	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	534.000	SD
0470	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,148.000	SD
0480	880(E)6607	WARNING LIGHTS(TYPE B)	4,272.000	SD
0490	880(F)6700	DRUMS	29,486.000	SD
0500	880(G)6805	CHANNELIZER CONES	4,554.000	SD
0510	880(I)7000	FLAGGER	506.000	SD
0520	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	534.000	SD
0004	STAKING			
0530	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0540	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0550	641 2110	MOBILIZATION	1.000	LSUM