Proposal: 250087 **Let Date:** March 20, 2025 **Call Order:** 635
J/P Num: 34486(04) **Proj. Num:** STP-254D(073)CI
Counties: OKFUSKEE
Description: BRIDGE AND APPROACHES
COUNTY ROAD (NS-371): OVER UNNAMED
TRIBUTARY TO THE NORTH CANADIAN RIVER,
1.05 MILES NORTH OF SH-56 NEAR OKEMAH.
PROJECT LENGTH = 0.090 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	7,000.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	800.000	LF
0050	221(E)2600	TEMPORARY SILT DIKE	140.000	LF
0060	230(A)7200	SOLID SLAB SODDING	3,700.000	SY
0070	233(A)0200	VEGETATIVE MULCHING	0.900	AC
0080	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	550.000	TON
0090	601(A)1100	TYPE I PLAIN RIPRAP	400.000	TON
0100	613(B)5516	24" CORR. GALV. STEEL PIPE	42.000	LF
0110	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0120	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0130	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	1,390.000	LF
0002	BRIDGE NBI 33130			
0140	202(A)2210	UNCLASSIFIED EXCAVATION	2,405.000	CY
0150	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	282.000	CY
0160	509(A)0210	CLASS AA CONCRETE	462.100	CY
0170	511(A)2210	REINFORCING STEEL	69,350.000	LB
0180	601(A)1110	TYPE I PLAIN RIPRAP	2,200.000	TON
0190	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TEMPORARY TRAFFIC			
0200	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,160.000	SD
0210	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	240.000	SD
0220	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0230	880(E)6600	WARNING LIGHTS(TYPE A)	3,600.000	SD
0004	STAKING			
0240	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0250	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0260	641 2110	MOBILIZATION	1.000	LSUM