Proposal: 250089 **Let Date:** March 20, 2025 **Call Order:** 645
J/P Num: 38463(04) **Proj. Num:** STP-260C(098)CI
Counties: PAYNE
Description: RESURFACE (ASPHALT)
COUNTY ROAD (N EUCHEE VALLEY ROAD):
FROM THE INTERSECTION OF SH-33,
EXTEND NORTH AND WEST NEAR CUSHING.
PROJECT LENGTH = 3.981 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(D)2500	UNCLASSIFIED BORROW	180.000	CY
0020	221(B)2300	TEMPORARY SILT FENCE	4,375.000	LF
0030	230(A)7200	SOLID SLAB SODDING	7,450.000	SY
0040	303(A)1200	AGGREGATE BASE TYPE A	4,600.000	CY
0050	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	100.000	TON
0060	407(B)7300	TACK COAT	9,015.000	GAL
0070	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	7,023.000	TON
0080	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	5,102.000	TON
0090	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	936.000	TON
0100	412 3100	COLD MILLING PAVEMENT	58,479.000	SY
0110	629(D)7500	REMOVE AND RESET MAILBOX	18.000	EA
0002	TRAFFIC			
0120	853 5125	DELINEATORS(TYPE 2, CODE 3)	18.000	EA
0130	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,350.000	SD
0140	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	300.000	SD
0150	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	450.000	SD
0160	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	450.000	SD
0170	880(E)6600	WARNING LIGHTS(TYPE A)	900.000	SD
0180	880(G)6805	CHANNELIZER CONES	2,500.000	SD
0190	880(I)7000	FLAGGER	150.000	SD
0003	SIGNING AND STRIPING			
0200	850(A)1200	SHEET ALUMINUM SIGNS	280.000	SF
0210	851(C)2420	2 1/4" SQUARE TUBE POST	600.000	LF
0220	854(A)6201	(SP) TRAFFIC STRIPE(PAINT)(4" WIDE)	84,710.000	LF
0004	STAKING			
0230	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0240	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0250	641 2110	MOBILIZATION	1.000	LSUM