Proposal: 250090 **Let Date:** May 15, 2025 **Call Order:** 240
J/P Num: 35649(04) **Proj. Num:** STP-263C(118)PM
Counties: POTTAWATOMIE
Description: RESURFACE (ASPHALT)
SH-3E (E HIGHLAND STREET): FROM 46 FEET
EAST OF THE SH-18 (N HARRISON AVE) INTERSECTION,
EXTEND EAST NEAR SHAWNEE.
PROJECT LENGTH = 7.10 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(D)2500	UNCLASSIFIED BORROW	687.000	CY
0020	209 9100	MACHINE GRADING	39,851.000	LF
0030	407(B)7300	TACK COAT	28,333.000	GAL
0040	411(D)1530	SUPERPAVE, TYPE S5(PG 64-22 OK)	21,549.000	TON
0050	412 3100	COLD MILLING PAVEMENT	70,137.000	SY
0060	619(B)6396	REMOVAL OF GUARDRAIL	1,600.000	LF
0070	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	1,225.000	LF
0080	623(G)1820	GUARDRAIL END TREATMENT (31")	8.000	EA
0002	TRAFFIC			
0090	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	23,766.000	LF
0100	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	49,690.000	LF
0110	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	34.000	EA
0120	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	156,699.000	LF
0130	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	600.000	LF
0140	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	1,400.000	LF
0150	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	300.000	LF
0160	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	21.000	EA
0170	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	2.000	EA
0180	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,007.000	SD
0190	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,552.000	SD
0200	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	7,590.000	SD
0210	880(E)6607	WARNING LIGHTS(TYPE B)	7,590.000	SD
0220	880(I)7000	FLAGGER	90.000	SD
0230	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	208.000	SD