**Proposal:** 250091 **Let Date:** May 15, 2025 **Call Order:** 241
**J/P Num:** 38587(04) **Proj. Num:** NHPP-266N(142)PM
**Counties:** ROGERS
**Description:** RESURFACE (ASPHALT)
SH-66/SH-20/SH-88: SH-66, FROM 2.7 MILES SOUTHWEST OF THE SH-88 INTERSECTION EXTEND NORTHEAST IN CLAREMORE. SH-20/SH-88, FROM SH-66 EXTEND NORTHWEST IN CLAREMORE. PROJECT LENGTH = 5.56 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0001** | ROADWAY | | | |
| 0010 | 202(A)2200 | UNCLASSIFIED EXCAVATION | 500.000 | CY |
| 0020 | 303(A)1200 | AGGREGATE BASE TYPE A | 396.000 | CY |
| 0030 | 407(B)7300 | TACK COAT | 17,220.000 | GAL |
| 0040 | 411(C)1400 | SUPERPAVE, TYPE S4(PG 76-28 OK) | 20,755.000 | TON |
| 0050 | 411(C)1430 | SUPERPAVE, TYPE S4(PG 64-22 OK) | 4,564.000 | TON |
| 0060 | 411(H)1900 | SUPERPAVE, TYPE S3(PATCH)(PG64-22OK) | 697.000 | TON |
| 0070 | 411(I)2010 | SUPERPAVE, TYPE S4(PATCH)(PG76-28OK) | 200.000 | TON |
| 0080 | 412 3100 | COLD MILLING PAVEMENT | 226,044.000 | SY |
| 0090 | 609(A)4240 | CONC.CURB(6" BARRIER-DOWELLED) | 1,000.000 | LF |
| 0100 | 619(B)6376 | REMOVAL OF CONC.PAV.W/ASPH.OVERLAY | 1,778.000 | SY |
| 0110 | 619(C)6600 | SAWING PAVEMENT | 1,600.000 | LF |
| **0002** | TRAFFIC CONTROL | | | |
| 0120 | 104 3250 | (SP) RAILROAD FLAGGING(NON-BIDDABLE) | 30.000 | DAY |
| 0130 | 876(A)3210 | (PL)TRUCK MOUNTED ATTENUATOR | 180.000 | SD |
| 0140 | 880(A)6220 | ARROW DISPLAY(TYPE C) | 180.000 | SD |
| 0150 | 880(B)6300 | CONSTRUCTION SIGNS 0 TO 6.25 SF | 900.000 | SD |
| 0160 | 880(B)6310 | CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF | 7,020.000 | SD |
| 0170 | 880(B)6320 | CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF | 900.000 | SD |
| 0180 | 880(C)6410 | CONSTRUCTION BARRICADES(TYPE III) | 3,240.000 | SD |
| 0190 | 880(E)6600 | WARNING LIGHTS(TYPE A) | 6,480.000 | SD |
| 0200 | 880(E)6607 | WARNING LIGHTS(TYPE B) | 10,800.000 | SD |
| 0210 | 880(E)6616 | WARNING LIGHTS(TYPE D) | 8,100.000 | SD |
| 0220 | 880(F)6700 | DRUMS | 8,100.000 | SD |
| 0230 | 880(G)6805 | CHANNELIZER CONES | 10,800.000 | SD |
| 0240 | 882(A)8210 | PORT.CHANGEABLE MESSAGE SIGN | 388.000 | SD |
| **0003** | TRAFFIC SIGNING AND STRIPING | | | |
| 0250 | 856(A)8207 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE) | 128,170.000 | LF |
| 0260 | 856(A)8211 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE) | 824.000 | LF |
| 0270 | 856(A)8219 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE) | 3,304.000 | LF |
| 0280 | 856(B)8307 | (SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS) | 169.000 | EA |
| 0290 | 856(B)8311 | (SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS) | 8.000 | EA |
| 0300 | 856(B)8315 | (SP) TRAFFIC STRIPE(PLURAL-COMP)(WORDS) | 24.000 | EA |
| **0004** | STAKING | | | |
| 0310 | 642(B)3300 | CONSTRUCTION STAKING LEVEL II | 1.000 | LSUM |
| **0005** | CONSTRUCTION | | | |
| 0320 | 641 2110 | MOBILIZATION | 1.000 | LSUM |