Proposal: 250094 **Let Date:** August 14, 2025 **Call Order:** 885
J/P Num: 35940(04) **Proj. Num:** STP-272B(430)IG
Counties: TULSA
Description: PAVEMENT REHABILITATION (ASPHALT)
CITY STREET (WEST 41ST STREET): FROM THE SH-97 (WILSON AVENUE) JUNCTION, EXTEND WEST IN THE CITY OF SAND SPRINGS.
PROJECT LENGTH = 1.154 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(D)2520	UNCLASSIFIED BORROW (TOPSOIL)	19.000	CY
0020	221(B)2300	TEMPORARY SILT FENCE	500.000	LF
0030	221(G)2800	TEMPORARY FIBER LOG	585.000	LF
0040	230(A)7200	SOLID SLAB SODDING	500.000	SY
0050	303(A)1200	AGGREGATE BASE TYPE A	749.000	CY
0060	310(B)5300	SUBGRADE, METHOD B	2,137.000	SY
0070	325 0100	SEPARATOR FABRIC	2,137.000	SY
0080	407(B)7300	TACK COAT	2,343.000	GAL
0090	408 8100	PRIME COAT	534.000	GAL
0100	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	838.000	TON
0110	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	3,353.000	TON
0120	412 3100	COLD MILLING PAVEMENT	26,904.000	SY
0130	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	27.000	LF
0140	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	476.000	LF
0150	610(A)5200	4" CONCRETE SIDEWALK	448.000	SY
0160	610(I)6000	TACTILE WARNING DEVICE-NEW	353.000	SF
0170	612(A)3200	MANHOLES ADJUST TO GRADE	7.000	EA
0180	612(E)3600	VALVE BOXES ADJUST TO GRADE	4.000	EA
0190	619(B)6356	REMOVAL OF CURB AND GUTTER	518.000	LF
0200	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	2,137.000	SY
0210	619(B)6404	REMOVAL OF SIDEWALK	601.000	SY
0002	TRAFFIC			
0220	805(A)3200	REMOVAL OF SIGN FOOTING	51.000	EA
0230	805(A)3204	REMOVAL OF CLASS C PAVEMENT MARKERS	339.000	EA
0240	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	51.000	EA
0250	805(D)3536	(PL)REMOVE & RESET GROUND MOUNTED SIGN	9.000	EA
0260	850(A)1200	SHEET ALUMINUM SIGNS	322.000	SF
0270	851(C)2415	2" SQUARE TUBE POST	510.000	LF
0280	851(C)2430	2 1/2" SQUARE TUBE POST	128.000	LF
0290	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	18,196.000	LF
0300	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	506.000	LF
0310	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	1,214.000	LF
0320	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	33.000	EA
0330	856(B)8315	(SP) TRAFFIC STRIPE(PLURAL-COMP)(WORDS)	4.000	EA
0340	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	900.000	EA
0350	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	1,891.000	LF
0360	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	6,416.000	SD
0370	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,716.000	SD
0380	880(E)6600	WARNING LIGHTS(TYPE A)	5,432.000	SD
0390	880(F)6700	DRUMS	5,880.000	SD
0400	880(G)6800	TUBE CHANNELIZERS	45,752.000	SD
0410	880(I)7000	FLAGGER	40.000	SD
0003	STAKING			
0420	642(A)3200	CONSTRUCTION STAKING LEVEL I	1.000	LSUM

Proposal: 250094 **Let Date:** August 14, 2025 **Call Order:** 885
J/P Num: 35940(04) **Proj. Num:** STP-272B(430)IG
Counties: TULSA
Description: PAVEMENT REHABILITATION (ASPHALT)
CITY STREET (WEST 41ST STREET): FROM THE SH-97 (WILSON AVENUE) JUNCTION, EXTEND WEST IN THE CITY OF SAND SPRINGS.
PROJECT LENGTH = 1.154 MILES

Line #		Item Description	Quantity	Unit
0004	CONSTRUCTION			
0430	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0440	641 2110	MOBILIZATION	1.000	LSUM