Proposal: 250095 **Let Date:** March 20, 2025 **Call Order:** 675
J/P Num: 33925(04) **Proj. Num:** STP-275D(080)CI
Counties: WASHITA
Description: BRIDGE AND APPROACHES
COUNTY ROAD (EW-112): OVER COFFEE CREEK,
1.0 MILES NORTH OF SH-54A NEAR CORN.
PROJECT LENGTH = 0.161 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(H)2900	EARTHWORK	1.000	LSUM
0030	221(B)2300	TEMPORARY SILT FENCE	200.000	LF
0040	221(E)2600	TEMPORARY SILT DIKE	200.000	LF
0050	230(A)7200	SOLID SLAB SODDING	6,000.000	SY
0060	233(A)0200	VEGETATIVE MULCHING	1.250	AC
0070	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	486.000	TON
0080	509(D)0500	CLASS C CONCRETE	93.000	CY
0090	613(B)5528	36" CORR. GALV. STEEL PIPE	65.000	LF
0100	613(M)6912	TYPE D3 CULVERT END TREATMENT	2.000	EA
0110	619(B)6440	REMOVAL OF EXISTING PIPE	40.000	LF
0002	BRIDGE			
0120	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	230.600	CY
0130	501(F)1700	GRANULAR BACKFILL	109.600	CY
0140	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	399.000	LF
0150	504(D)5410	CONCRETE RAIL (TR3)	281.300	LF
0160	506(A)7200	STRUCTURAL STEEL	660.000	LB
0170	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	4.000	EA
0180	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	4.000	EA
0190	509(A)0210	CLASS AA CONCRETE	89.400	CY
0200	509(B)0320	CLASS A CONCRETE	83.200	CY
0210	511(A)2210	REINFORCING STEEL	34,572.000	LB
0220	514(A)5210	PILES, FURNISHED (HP 10X42)	120.000	LF
0230	514(A)5220	PILES, FURNISHED (HP 12X53)	420.000	LF
0240	514(B)5310	PILES, DRIVEN (HP 10X42)	120.000	LF
0250	514(B)5320	PILES, DRIVEN (HP 12X53)	420.000	LF
0260	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0270	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	3,980.000	TON
0280	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	66.000	LF
0290	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	38.000	LF
0300	623(F)1748	GUARDRAIL ANCHOR UNIT (TYPE II)	4.000	EA
0003	TRAFFIC			
0310	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	360.000	SD
0320	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	540.000	SD
0330	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	900.000	SD
0340	880(E)6600	WARNING LIGHTS(TYPE A)	1,980.000	SD
0004	STAKING			
0350	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0360	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0370	641 2110	MOBILIZATION	1.000	LSUM