Proposal: 250096 **Let Date:** June 19, 2025 **Call Order:** 485
J/P Num: 38283(04) **Proj. Num:** NHPP-017N(312)3P
Counties: WOODWARD
Description: RESURFACE (ASPHALT)
US-183: FROM THE INTERSECTION OF SH-50,
EXTEND NORTHWEST NEAR WOODWARD.
PROJECT LENGTH = 8.00 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	407(C)7400	(SP) POLYMER MOD. CATIONIC RAPID SET - 1S	57,650.000	GAL
0020	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	25,850.000	TON
0030	412 3100	COLD MILLING PAVEMENT	231,000.000	SY
0002	TRAFFIC			
0040	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	192,000.000	LF
0050	880(A)6220	ARROW DISPLAY(TYPE C)	90.000	SD
0060	880(J)7100	(SP) CONSTRUCTION TRAFFIC CONTROL	45.000	SD
0070	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	90.000	SD
0003	CONSTRUCTION			
0080	641 2110	MOBILIZATION	1.000	LSUM