Proposal:250097 **Let Date:**April 17, 2025 **Call Order:**837
J/P Num:34108(04) **Proj. Num:**TAP-221D(077)TP
Counties:DELAWARE
Description:SIDEWALK AND PEDESTRIAN IMPROVEMENT
CITY STREET (MONROE STREET):
FROM 0.73 MILES WEST OF US-59 / SH-10, EXTEND EAST IN THE CITY OF JAY.
PROJECT LENGTH = 0.500 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY - BASE BID - TAP-221D(077)TP			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	200.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	200.000	CY
0030	221(B)2300	TEMPORARY SILT FENCE	2,600.000	LF
0040	221(G)2800	TEMPORARY FIBER LOG	100.000	LF
0050	230(A)7200	SOLID SLAB SODDING	1,408.800	SY
0060	240(A)2200	REMOVING TREES 6" TO 12" IN DIAMETER	2.000	EA
0070	240(A)2220	REMOVING TREES 19" TO 24" IN DIAMETER	3.000	EA
0080	240(A)2230	REMOVING TREES 25" & MORE IN DIAMETER	1.000	EA
0090	303(A)1200	AGGREGATE BASE TYPE A	271.300	CY
0100	325 0100	SEPARATOR FABRIC	100.000	SY
0110	326(B)1300	GEOGRID REINFORCEMENT	100.000	SY
0120	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	38.100	TON
0130	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	9.800	TON
0140	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	4.300	CY
0150	610(A)5200	4" CONCRETE SIDEWALK	1,262.500	SY
0160	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	208.400	SY
0170	610(I)6000	TACTILE WARNING DEVICE-NEW	120.000	SF
0180	612(A)3200	MANHOLES ADJUST TO GRADE	1.000	EA
0190	613(B)5680	PVC DRAINAGE STRUCTURE	7.000	EA
0200	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	173.800	SY
0210	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	158.200	SY
0220	619(B)6404	REMOVAL OF SIDEWALK	127.400	SY
0230	632 0100	(PL) SITESCAPING	1.000	LSUM
0002	TRAFFIC - BASE BID - TAP-221D(077)TP			
0240	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	4.000	EA
0250	805(B)3300	(PL)RESET OF PULL BOX	3.000	EA
0270	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	3.000	EA
0280	850(A)1200	SHEET ALUMINUM SIGNS	55.000	SF
0290	851(C)2415	2" SQUARE TUBE POST	132.000	LF
0300	855(A)7217	(SP) TRAFFIC STRIPE(PLASTIC)(24" WIDE)	320.500	LF
0310	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	810.000	SD
0320	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	540.000	SD
0330	880(E)6610	WARNING LIGHTS(TYPE C)	2,160.000	SD
0340	880(F)6700	DRUMS	2,160.000	SD

Proposal:250097 **Let Date:**April 17, 2025 **Call Order:**837
J/P Num:34108(04) **Proj. Num:**TAP-221D(077)TP
Counties:DELAWARE
Description:SIDEWALK AND PEDESTRIAN IMPROVEMENT
CITY STREET (MONROE STREET):
FROM 0.73 MILES WEST OF US-59 / SH-10, EXTEND EAST IN THE CITY OF JAY.
PROJECT LENGTH = 0.500 MILES

Line #		Item Description	Quantity	Unit
0003	ROADWAY - ADD ALT. #1 - TAP-221D(077)TP			
0350	221(B)2300	TEMPORARY SILT FENCE	1,200.000	LF
0360	221(G)2800	TEMPORARY FIBER LOG	100.000	LF
0370	230(A)7200	SOLID SLAB SODDING	883.600	SY
0380	303(A)1200	AGGREGATE BASE TYPE A	118.000	CY
0390	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	12.000	TON
0400	610(A)5200	4" CONCRETE SIDEWALK	694.000	SY
0410	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	13.900	SY
0420	610(I)6000	TACTILE WARNING DEVICE-NEW	20.000	SF
0430	613(A)5216	24" R.C.PIPE CLASS III	30.000	LF
0440	613(M)6992	TYPE DD4 CULVERT END TREATMENT	4.000	EA
0450	619(B)6436	REMOVAL OF CONCRETE DITCH LINER	8.000	LF
0004	TRAFFIC - ADD ALT. #1 - TAP-221D(077)TP			
0470	836 7110	RECTANGULAR RAPID FLASHING BEACON	1.000	EA
0480	850(A)1200	SHEET ALUMINUM SIGNS	10.000	SF
0490	851(C)2415	2" SQUARE TUBE POST	24.000	LF
0500	855(A)7217	(SP) TRAFFIC STRIPE(PLASTIC)(24" WIDE)	49.400	LF
0510	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	135.000	SD
0520	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	90.000	SD
0530	880(E)6610	WARNING LIGHTS(TYPE C)	360.000	SD
0540	880(F)6700	DRUMS	360.000	SD
0005	STAKING - TAP-221D(077)TP			
0550	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION - TAP-221D(077)TP			
0560	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0570	641 2100	MOBILIZATION	1.000	LSUM