Proposal: 250105 **Let Date:** March 13, 2025 **Call Order:** 537
J/P Num: 38215(04) **Proj. Num:** SSR-020N(070)SR
Counties: JACKSON, TILLMAN
Description: RESURFACE (ASPHALT)
US-62: FROM 10.35 MILES EAST OF THE US-283 INTERSECTION, EXTEND EAST NEAR SNYDER.
PROJECT LENGTH = 7.89 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	407(C)7400	(SP) POLYMER MOD. CATIONIC RAPID SET - 1S	69,625.000	GAL
0020	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	42,675.000	TON
0030	412 3100	COLD MILLING PAVEMENT	32,523.000	SY
0040	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	76,000.000	LF
0050	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	80,000.000	LF
0002	TRAFFIC SIGNING AND STRIPING			
0060	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	212,000.000	LF
0070	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	500.000	LF
0080	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	450.000	LF
0090	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	30.000	LF
0100	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	125.000	EA
0003	TRAFFIC CONTROL			
0110	857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	16,681.000	EA
0120	880(A)6220	ARROW DISPLAY(TYPE C)	75.000	SD
0130	880(J)7100	(SP) CONSTRUCTION TRAFFIC CONTROL	75.000	SD
0140	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	178.000	SD