Proposal: 250108 **Let Date:** November 13, 2025 **Call Order:** 530
J/P Num: 34908(04) **Proj. Num:** CIRB-250C(055)RB
Counties: MURRAY
Description: BRIDGE REHABILITATION
COUNTY ROAD (KAY STARR TRAIL): OVER THE WASHITA RIVER, 6.4 MILES SOUTHEAST OF THE US-77 INTERSECTION NEAR DOUGHERTY.
PROJECT LENGTH = 0.198 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	821.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	290.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	1,382.000	LF
0060	221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	50.000	CY
0070	233(A)0200	VEGETATIVE MULCHING	1.660	AC
0080	233(F)0700	(SP) HYDROSEED	1,771.000	SY
0090	303(A)1200	AGGREGATE BASE TYPE A	286.000	CY
0100	325 0100	SEPARATOR FABRIC	2,525.000	SY
0110	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	384.000	TON
0120	407(B)7300	TACK COAT	89.000	GAL
0130	408 8100	PRIME COAT	1,600.000	GAL
0140	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	254.000	TON
0150	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	258.000	TON
0160	509(D)0500	CLASS C CONCRETE	10.000	CY
0170	602(B)2310	REVETMENT MATTRESSES	3,485.000	SY
0180	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0190	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,492.000	SY
0200	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	879.500	LF
0210	623(F)1704	GUARDRAIL ANCHOR UNIT (TYPE A)	4.000	EA
0220	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	115.000	LF

Proposal:250108 **Let Date:**November 13, 2025 **Call Order:**530
J/P Num:34908(04) **Proj. Num:**CIRB-250C(055)RB
Counties:MURRAY
Description:BRIDGE REHABILITATION
COUNTY ROAD (KAY STARR TRAIL): OVER THE WASHITA RIVER, 6.4 MILES SOUTHEAST OF THE US-77 INTERSECTION NEAR DOUGHERTY.
PROJECT LENGTH = 0.198 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE			
0230	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	100.000	CY
0240	501(G)1800	CLSM BACKFILL	63.600	CY
0250	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0260	502(B)3320	(PL)FALSEWORK JACKING	1.000	LSUM
0270	504(B)5300	SAW-CUT GROOVING	12.000	SY
0280	506(A)7200	STRUCTURAL STEEL	1,020.000	LB
0290	509(A)0210	CLASS AA CONCRETE	2.800	CY
0300	509(B)0320	CLASS A CONCRETE	6.000	CY
0310	511 2100	MECHANICAL SPLICES	36.000	EA
0320	511(B)2310	EPOXY COATED REINFORCING STEEL	1,600.000	LB
0330	512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0340	512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0350	513(B)4300	CLASS B BRIDGE DECK REPAIR	10.000	SY
0360	513(C)4400	CLASS C BRIDGE DECK REPAIR	10.000	SY
0370	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	168.000	SY
0380	517 9110	ELASTOMERIC COATING	711.000	SF
0390	518(C)0400	RAPID CURE JOINT SEALANT	490.000	LF
0400	518(J)0800	PREFORMED SILICONE FOAM JOINTS	50.000	LF
0410	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	110.000	LF
0420	520(C)1400	EPOXY RESIN, ABOVE WATER	8.800	GAL
0430	521(A)2200	PNEUMATICALLY PLACED MORTAR	21.000	SY
0440	523(C)3400	DECK AREA SEALED (FLOODCOATS)	1,072.000	SY
0450	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	41.000	SY
0460	540 8120	(PL)REPAIR BRIDGE ITEM (TYPE A)	5.000	EA
0470	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0003	TRAFFIC			
0480	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	138.000	SD
0490	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	2,100.000	LF
0500	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	240.000	LF
0510	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	500.000	LF
0520	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	500.000	LF
0530	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,484.000	SD
0540	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	690.000	SD
0550	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,070.000	SD
0560	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	552.000	SD
0570	880(E)6600	WARNING LIGHTS(TYPE A)	7,590.000	SD
0580	880(F)6700	DRUMS	4,692.000	SD
0590	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	292.000	SD
0004	STAKING			
0600	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0610	641 2110	MOBILIZATION	1.000	LSUM