Proposal: 250110 **Let Date:** July 17, 2025 **Call Order:** 620
J/P Num: 30496(04) **Proj. Num:** STP-253D(068)CI
Counties: NOWATA
Description: BRIDGE AND APPROACHES
COUNTY ROAD (NS 413 RD): OVER HICKORY CREEK,
1.0 MILE WEST OF US-169 NEAR LENAPAH.
PROJECT LENGTH = 0.472 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	10,077.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	3,162.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	210 0100	OBLITERATING ABANDONED ROAD	1,796.000	LF
0060	221(B)2300	TEMPORARY SILT FENCE	4,564.000	LF
0070	221(E)2600	TEMPORARY SILT DIKE	392.000	LF
0080	230(A)7200	SOLID SLAB SODDING	34,229.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	9.420	AC
0100	303(A)1200	AGGREGATE BASE TYPE A	1,923.000	CY
0110	509(D)0500	CLASS C CONCRETE	10.000	CY
0120	601(B)1220	TYPE I-A PLAIN RIPRAP	333.000	TON
0130	601(C)1300	TYPE I-A FILTER BLANKET	140.000	TON
0140	613(A)5208	18" R.C.PIPE CLASS III	41.000	LF
0150	613(B)5508	18" CORR. GALV. STEEL PIPE	318.000	LF
0160	613(M)6960	TYPE A4 CULVERT END TREATMENT	11.000	EA
0170	613(N)7100	TYPE A4 SLOPED CONCRETE END SECTION	1.000	EA
0180	613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	11.000	CY
0190	613(V)8000	TRENCH EXCAVATION	24.000	CY
0200	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0210	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	2,185.000	LF
0220	629(A)7200	MAILBOX INSTALLATION-SINGLE	1.000	EA
0230	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	1.000	EA
0240	629(E)7600	MAILBOX	1.000	EA

Proposal:250110 **Let Date:**July 17, 2025 **Call Order:**620
J/P Num:30496(04) **Proj. Num:**STP-253D(068)CI
Counties:NOWATA
Description:BRIDGE AND APPROACHES
COUNTY ROAD (NS 413 RD): OVER HICKORY CREEK,
1.0 MILE WEST OF US-169 NEAR LENAPAH.
PROJECT LENGTH = 0.472 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE			
0250	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	220.000	CY
0260	501(G)1800	CLSM BACKFILL	102.000	CY
0270	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	299.000	LF
0280	504(D)5410	CONCRETE RAIL (TR3)	281.300	LF
0290	506(A)7200	STRUCTURAL STEEL	590.000	LB
0300	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	3.000	EA
0310	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	3.000	EA
0320	509(A)0210	CLASS AA CONCRETE	81.400	CY
0330	509(B)0320	CLASS A CONCRETE	79.400	CY
0340	511(A)2210	REINFORCING STEEL	34,039.000	LB
0350	514(A)5210	PILES, FURNISHED (HP 10X42)	84.000	LF
0360	514(A)5220	PILES, FURNISHED (HP 12X53)	252.000	LF
0370	514(B)5310	PILES, DRIVEN (HP 10X42)	84.000	LF
0380	514(B)5320	PILES, DRIVEN (HP 12X53)	252.000	LF
0390	514(K)6200	(PL)PILOT HOLES	182.000	LF
0400	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0410	601(B)1230	TYPE I-A PLAIN RIPRAP	4,405.000	TON
0420	601(C)1310	TYPE I-A FILTER BLANKET	535.000	TON
0430	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	60.000	LF
0440	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	50.000	LF
0450	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0460	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0003	TRAFFIC			
0470	623(A)1210	BEAM GUARDRAIL W-BEAM SINGLE	37.500	LF
0480	623(G)1800	GUARDRAIL END TREATMENT (GET)	3.000	EA
0490	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	480.000	SD
0500	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	480.000	SD
0510	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,440.000	SD
0520	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,440.000	SD
0530	880(E)6600	WARNING LIGHTS(TYPE A)	2,880.000	SD
0004	STAKING			
0540	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0550	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0560	641 2100	MOBILIZATION	1.000	LSUM