Proposal:250112 **Let Date:**July 10, 2025 **Call Order:**520
J/P Num:31170(04) **Proj. Num:**STP-258C(100)CI
Counties:OTTAWA
Description:GRADE, DRAIN, BRIDGE AND SURFACE
COUNTY ROADS (NS 4520 RD/EW 120 RD):
FROM THE INTERSECTION OF US-59, EXTEND SOUTH AND EAST NEAR MIAMI.
PROJECT LENGTH = 3.166 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	35,925.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	8,245.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	33,524.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	3,129.000	LF
0070	221(G)2800	TEMPORARY FIBER LOG	112.000	LF
0080	230(A)7200	SOLID SLAB SODDING	125,211.000	SY
0090	233(A)0200	VEGETATIVE MULCHING	25.870	AC
0100	303(A)1200	AGGREGATE BASE TYPE A	11,528.000	CY
0110	307(K)4200	STABILIZED SUBGRADE	55,513.000	SY
0120	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	55,513.000	SY
0130	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	2,787.000	TON
0140	407(B)7300	TACK COAT	3,835.000	GAL
0150	408 8100	PRIME COAT	14,010.000	GAL
0160	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	9,442.000	TON
0170	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	5,941.000	TON
0180	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	419.000	CY
0190	509(A)0200	CLASS AA CONCRETE	346.000	CY
0200	509(D)0500	CLASS C CONCRETE	394.900	CY
0210	511(A)2200	REINFORCING STEEL	48,939.000	LB
0220	601(B)1220	TYPE I-A PLAIN RIPRAP	1,129.000	TON
0230	601(C)1300	TYPE I-A FILTER BLANKET	568.000	TON
0240	610(B)5310	6" CONCRETE DRIVEWAY	26.000	SY
0250	611(G)0350	INLET (SMD-TYPE 1)	4.000	EA
0260	613(A)5216	24" R.C.PIPE CLASS III	84.000	LF
0270	613(A)5220	30" R.C.PIPE CLASS III	187.000	LF
0280	613(A)5224	36" R.C.PIPE CLASS III	96.000	LF
0290	613(A)5228	42" R.C.PIPE CLASS III	92.000	LF
0300	613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	398.000	LF
0310	613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	238.000	LF
0320	613(A)5366	36" X 22" R.C.PIPE ARCH CLASS A-III	124.000	LF
0330	613(A)5386	73" X 45" R.C.PIPE ARCH CLASS A-III	136.000	LF
0340	613(EE)5969	18" CORRUGATED POLYPROPYLENE PIPE	1,452.000	LF
0350	613(EE)5973	24" CORRUGATED POLYPROPYLENE PIPE	202.000	LF
0360	613(EE)5977	30" CORRUGATED POLYPROPYLENE PIPE	56.000	LF
0370	613(L)6612	22" X 13" PREFAB. CULVERT END SEC., ARCH	6.000	EA
0380	613(L)6620	28" X 18" PREFAB. CULVERT END SEC., ARCH	6.000	EA
0390	613(L)6636	36" X 22" PREFAB. CULVERT END SEC., ARCH	6.000	EA
0400	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0410	613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	10.000	EA
0420	613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0430	613(L)6732	42" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0440	613(M)6960	TYPE A4 CULVERT END TREATMENT	42.000	EA
0450	613(M)6964	TYPE B4 CULVERT END TREATMENT	10.000	EA
0460	613(M)6968	TYPE C4 CULVERT END TREATMENT	2.000	EA

Proposal:250112 **Let Date:**July 10, 2025 **Call Order:**520
J/P Num:31170(04) **Proj. Num:**STP-258C(100)CI
Counties:OTTAWA
Description:GRADE, DRAIN, BRIDGE AND SURFACE
COUNTY ROADS (NS 4520 RD/EW 120 RD):
FROM THE INTERSECTION OF US-59, EXTEND SOUTH AND EAST NEAR MIAMI.
PROJECT LENGTH = 3.166 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	613(M)6996	TYPE EE4 CULVERT END TREATMENT	2.000	EA
0480	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0490	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	11,558.000	SY
0500	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	26.000	SY
0510	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	321.000	SY
0520	619(C)6600	SAWING PAVEMENT	266.000	LF
0530	624(B)3350	GATES-STYLE WWF (4.5'HIGH X 14'LONG)	9.000	EA
0540	624(B)3360	GATES-STYLE WWF (4.5'HIGH X 16'LONG)	7.000	EA
0550	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	4,605.000	LF
0560	624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	11,767.000	LF
0570	624(D)3500	GATE, GALVANIZED STEEL	6.000	EA
0580	624(E)3620	FENCE-STYLE CLF (6'HIGH, CLASS A)	423.000	LF
0590	624(F)3775	GATES-STYLE CLF (6'HIGH X 18'LONG)	2.000	EA
0600	629(A)7200	MAILBOX INSTALLATION-SINGLE	10.000	EA
0610	629(B)7300	MAILBOX INSTALLATION-MULTIPLE	5.000	EA
0620	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	15.000	EA
0630	629(E)7600	MAILBOX	19.000	EA
0002	BRIDGE			
0640	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	220.000	CY
0650	501(C)1400	SUBSTRUCTURE EXCAVATION ROCK	20.000	CY
0660	501(G)1800	CLSM BACKFILL	102.000	CY
0670	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	299.000	LF
0680	504(B)5300	SAW-CUT GROOVING	254.400	SY
0690	504(D)5410	CONCRETE RAIL (TR3)	281.300	LF
0700	506(A)7200	STRUCTURAL STEEL	590.000	LB
0710	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	3.000	EA
0720	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	3.000	EA
0730	509(A)0210	CLASS AA CONCRETE	81.400	CY
0740	509(B)0320	CLASS A CONCRETE	79.400	CY
0750	511(A)2210	REINFORCING STEEL	32,440.000	LB
0760	514(A)5210	PILES, FURNISHED (HP 10X42)	76.000	LF
0770	514(A)5220	PILES, FURNISHED (HP 12X53)	266.000	LF
0780	514(B)5310	PILES, DRIVEN (HP 10X42)	76.000	LF
0790	514(B)5320	PILES, DRIVEN (HP 12X53)	266.000	LF
0800	514(K)6200	(PL)PILOT HOLES	270.000	LF
0810	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0820	517 9110	ELASTOMERIC COATING	277.000	SF
0830	602(B)2300	ARTICULATING CONCRETE BLOCK	742.000	SF
0840	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	60.000	LF
0850	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	40.000	LF
0860	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:250112 **Let Date:**July 10, 2025 **Call Order:**520
J/P Num:31170(04) **Proj. Num:**STP-258C(100)CI
Counties:OTTAWA
Description:GRADE, DRAIN, BRIDGE AND SURFACE
COUNTY ROADS (NS 4520 RD/EW 120 RD):
FROM THE INTERSECTION OF US-59, EXTEND SOUTH AND EAST NEAR MIAMI.
PROJECT LENGTH = 3.166 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC			
0870	104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	1.000	DAY
0880	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0890	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0900	805(A)3248	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
0910	850(A)1200	SHEET ALUMINUM SIGNS	108.100	SF
0920	851(C)2420	2 1/4" SQUARE TUBE POST	156.000	LF
0930	853 5115	DELINEATORS(TYPE 2, CODE 1)	8.000	EA
0940	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	67,006.000	LF
0950	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	115.000	LF
0960	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	4.000	EA
0970	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	33,600.000	SD
0980	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,360.000	SD
0990	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,480.000	SD
1000	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,800.000	SD
1010	880(E)6600	WARNING LIGHTS(TYPE A)	11,600.000	SD
1020	880(F)6700	DRUMS	12,069.000	SD
1030	880(G)6805	CHANNELIZER CONES	12,069.000	SD
1040	880(I)7000	FLAGGER	480.000	SD
1050	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	320.000	SD
0004	STAKING			
1060	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
1070	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1080	641 2100	MOBILIZATION	1.000	LSUM