Proposal: 250113 **Let Date:** March 20, 2025 **Call Order:** 571
J/P Num: 35641(04) **Proj. Num:** SBR-3500(188)SB
Counties: PAYNE
Description: BRIDGE REHABILITATION
I-35: OVER COUNTY ROAD (E 0650 RD),
2.98 MILES SOUTH OF SH-51 NEAR GUTHRIE.
PROJECT LENGTH = 0.019 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	127.000	CY
0030	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040	221(B)2300	TEMPORARY SILT FENCE	885.000	LF
0050	230(A)7200	SOLID SLAB SODDING	296.000	SY
0060	303(A)1200	AGGREGATE BASE TYPE A	127.000	CY
0070	325 0100	SEPARATOR FABRIC	564.000	SY
0080	408 8100	PRIME COAT	164.000	GAL
0090	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	113.000	TON
0100	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	466.000	SY
0110	619(B)6396	REMOVAL OF GUARDRAIL	747.000	LF
0120	619(C)6600	SAWING PAVEMENT	885.000	LF
0002	BRIDGE A			
0130	501(G)1800	CLSM BACKFILL	160.000	CY
0140	504(A)5200	APPROACH SLAB	191.000	SY
0150	504(B)5300	SAW-CUT GROOVING	324.500	SY
0160	504(E)5520	42" F-SHAPED PARAPET	283.000	LF
0170	506(A)7200	STRUCTURAL STEEL	210.000	LB
0180	507(C)8400	ELASTOMERIC BEARING PADS	8.000	EA
0190	509(A)0210	CLASS AA CONCRETE	128.100	CY
0200	509(D)0510	CLASS C CONCRETE	20.000	CY
0210	511(A)2210	REINFORCING STEEL	800.000	LB
0220	511(B)2310	EPOXY COATED REINFORCING STEEL	28,920.000	LB
0230	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	138.400	SY
0240	517 9110	ELASTOMERIC COATING	238.000	SF
0250	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	60.000	LF
0260	520(C)1400	EPOXY RESIN, ABOVE WATER	6.000	GAL
0270	521(A)2200	PNEUMATICALLY PLACED MORTAR	64.000	SY
0280	523(A)3200	SEALER CRACK PREPARATION	283.000	LF
0290	523(B)3300	SEALER RESIN	3.200	GAL
0300	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0003	TRAFFIC			
0310	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	633.000	LF
0320	623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
0330	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	2.000	EA
0340	853 5100	DELINEATORS(TYPE 1, CODE 1)	16.000	EA
0350	856(A)8206	(SP) TRAFFIC STRIPE(MULTI-POLY.)(6" WIDE)	1,610.000	LF
0360	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	1,244.000	LF

Proposal:250113 **Let Date:**March 20, 2025 **Call Order:**571
J/P Num:35641(04) **Proj. Num:**SBR-3500(188)SB
Counties:PAYNE
Description:BRIDGE REHABILITATION
I-35: OVER COUNTY ROAD (E 0650 RD),
2.98 MILES SOUTH OF SH-51 NEAR GUTHRIE.
PROJECT LENGTH = 0.019 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC CONTROL			
0370	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	2,356.000	EA
0380	871(B)2300	CONST.ZONE IMPACT ATTEN.	180.000	SD
0390	871(C)2410	RELOCATION OF IMPACT ATTENUATOR	1.000	EA
0400	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	950.000	LF
0410	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	950.000	LF
0420	880(A)6220	ARROW DISPLAY(TYPE C)	180.000	SD
0430	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	5,400.000	SD
0440	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,980.000	SD
0450	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,240.000	SD
0460	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,520.000	SD
0470	880(C)6420	WING BARRICADES	360.000	SD
0480	880(E)6600	WARNING LIGHTS(TYPE A)	1,440.000	SD
0490	880(F)6700	DRUMS	12,240.000	SD
0500	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	195.000	SD
0005	STAKING			
0510	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0520	641 2100	MOBILIZATION	1.000	LSUM