Proposal: 250116 **Let Date:** March 13, 2025 **Call Order:** 573
J/P Num: 35653(04) **Proj. Num:** SSR-012N(118)SR
Counties: SEMINOLE
Description: RESURFACE (ASPHALT)
SH-99: FROM 2.04 MILES NORTH OF US-270 (SH-9),
EXTEND NORTH NEAR SEMINOLE.
PROJECT LENGTH = 8.52 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	407(C)7500	NT TACK MATERIAL	27,245.000	GAL
0020	411(D)1520	SUPERPAVE, TYPE S5(PG 70-28 OK)	20,638.000	TON
0030	412 3100	COLD MILLING PAVEMENT	233,986.000	SY
0002	TRAFFIC			
0040	855(A)7205	(SP) TRAFFIC STRIPE(PLASTIC)(6" WIDE)	214,183.000	LF
0050	855(A)7213	(SP) TRAFFIC STRIPE(PLASTIC)(12" WIDE)	4,050.000	LF
0060	855(B)7305	(SP) TRAFFIC STRIPE(PLASTIC)(ARROWS)	67.000	EA
0070	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	73,233.000	LF
0080	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	67.000	EA
0090	858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	1,118.000	EA
0095	880(A)6220	ARROW DISPLAY(TYPE C)	160.000	SD
0100	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,780.000	SD
0110	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,890.000	SD
0120	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	7,959.000	SD
0130	880(E)6607	WARNING LIGHTS(TYPE B)	2,310.000	SD
0135	880(F)6700	DRUMS	2,560.000	SD
0136	880(G)6805	CHANNELIZER CONES	8,798.000	SD
0140	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	224.000	SD