Proposal:250126 **Let Date:**January 15, 2026 **Call Order:**725
J/P Num:38003(04) **Proj. Num:**TAP-224C(113)TP
Counties:GARFIELD
Description:PEDESTRIAN AND BIKE IMPROVEMENTS
CITY STREET (MAIN ST): FROM 0.231 MILES WEST OF SH-74, EXTEND EAST IN THE TOWN OF COVINGTON.
PROJECT LENGTH = 0.45 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0015	202(A)2200	UNCLASSIFIED EXCAVATION	83.890	CY
0020	221(B)2300	TEMPORARY SILT FENCE	1,050.000	LF
0030	221(E)2600	TEMPORARY SILT DIKE	60.000	LF
0040	221(G)2800	TEMPORARY FIBER LOG	1,200.000	LF
0050	230(A)7200	SOLID SLAB SODDING	1,175.000	SY
0060	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	491.000	TON
0070	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	330.000	SY
0080	414(G)5800	P.C. CONCRETE FOR PAVEMENT	74.000	CY
0090	504(F)5600	HANDRAILING	24.000	LF
0100	535 7170	PREFABRICATED PEDESTRIAN BRIDGE	1.000	EA
0110	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	177.000	LF
0120	609(B)4315	COMBINED CURB & GUTTER(8" BARRIER)	54.000	LF
0130	609(C)4410	CONCRETE HEADER CURB (8"X 18")	593.000	LF
0140	610(A)5200	4" CONCRETE SIDEWALK	1,534.000	SY
0150	610(A)5210	5" CONCRETE SIDEWALK	15.000	SY
0160	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	195.000	SY
0170	610(I)6000	TACTILE WARNING DEVICE-NEW	160.000	SF
0180	612(E)3600	VALVE BOXES ADJUST TO GRADE	5.000	EA
0190	612(F)3700	METER BOXES ADJUST TO GRADE	10.000	EA
0200	612(I)4000	WATER METER RESET	2.000	EA
0210	613(B)5620	42" X 29" CORR. GALV. STEEL PIPE ARCH	10.000	LF
0220	613(P)7466	42" X 29" GALV. STEEL CULV. END SEC.ARCH	2.000	EA
0230	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	66.000	SY
0240	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	135.000	SY
0250	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	153.000	SY
0260	619(B)6400	REMOVAL OF CURB	171.000	LF
0270	619(B)6404	REMOVAL OF SIDEWALK	1,245.000	SY
0280	619(B)6456	REMOVAL OF PAVING BRICK ROADWAY	245.000	SY
0290	619(C)6600	SAWING PAVEMENT	996.000	LF
0300	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0310	802(B)0360	3" PVC SCH. 80 PLASTIC CONDUIT TRENCHED	40.000	LF
0002	SIGNING STRIPING AND SAFETY			
0320	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
0330	836 7110	RECTANGULAR RAPID FLASHING BEACON	4.000	EA
0340	850(A)1200	SHEET ALUMINUM SIGNS	26.260	SF
0350	851(C)2420	2 1/4" SQUARE TUBE POST	60.000	LF
0360	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	265.000	LF
0370	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	432.000	LF
0380	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	2.000	EA
0390	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	600.000	SD
0400	880(G)6805	CHANNELIZER CONES	1,050.000	SD
0003	STAKING			
0410	642(A)3200	CONSTRUCTION STAKING LEVEL I	1.000	LSUM

Proposal: 250126 **Let Date:** January 15, 2026 **Call Order:** 725
J/P Num: 38003(04) **Proj. Num:** TAP-224C(113)TP
Counties: GARFIELD
Description: PEDESTRIAN AND BIKE IMPROVEMENTS
CITY STREET (MAIN ST): FROM 0.231 MILES WEST OF SH-74, EXTEND EAST IN THE TOWN OF COVINGTON.
PROJECT LENGTH = 0.45 MILES

Line #		Item Description	Quantity	Unit
0004	CONSTRUCTION			
0420	641 2110	MOBILIZATION	1.000	LSUM