Proposal: 250127 **Let Date:** May 08, 2025 **Call Order:** 127
J/P Num: 38280(04) **Proj. Num:** STP-226C(132)3P
Counties: GRADY
Description: RESURFACE (ASPHALT)
SH-37: FROM 3.0 MILES WEST OF THE INTERSECTION OF SH-4, EXTEND EAST NEAR TUTTLE.
PROJECT LENGTH = 6.00 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	10,000.000	TON
0020	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	675.000	TON
0030	412 3100	COLD MILLING PAVEMENT	88,100.000	SY
0002	TRAFFIC			
0040	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	63,000.000	LF
0050	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	97,100.000	LF
0060	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	60.000	LF
0070	857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	450.000	LF
0080	880(A)6220	ARROW DISPLAY(TYPE C)	120.000	SD
0090	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,500.000	SD
0100	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	900.000	SD
0110	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,420.000	SD
0120	880(E)6600	WARNING LIGHTS(TYPE A)	318.000	SD
0130	880(G)6805	CHANNELIZER CONES	15,480.000	SD
0140	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	296.000	SD